



COLLEGE VIEW
ADDITION

ARRATIVE

THE PURPOSE OF THIS SURVEY WAS TO SURVEY THE PROPERTY LINE ADJUSTMENT BETWEEN LOT 1 & 2, PARTITION PLAT 1992-03, UMATILLA COUNTY.

THE PINS FOR THE PARTITION PLAT HAD JUST BEEN SET AND WERE FOUND AS SHOWN. THE BEARINGS ARE BASED UPON THE BEARINGS FOR THE COLLEGE VIEW PLAT. THE SURVEY WORK WAS DONE USING A WILDE T-1000.

CURVE	RADIUS	TANGENT	LENGTH	DELTA	DEGREE	CHORD	CH. BEARING
1	280.00'	77.84'	151.85'	31°04'25"	20°27'46"	150.00'	N 39°59'14"E
2	280.00'	18.41'	36.76'	7°31'22"	20°27'46"	36.74'	N 59°17'08"E

- INDICATES FOUND $\frac{5}{8}$ " x 30" IRON REBAR W/ALUMINUM CAP "PLS 933"
- INDICATES SET $\frac{5}{8}$ " x 30" IRON REBAR W/ALUMINUM CAP "PLS 933"

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon	Scale 1"=50'	Drn. By AST	Drng. No. 9207D	Revision 1
	Date 5-5-92	Ckd. By DHK	Job No. 91-48	Revision 2
PROPERTY LINE ADJUSTMENT WHITNEY NE $\frac{1}{4}$, SE $\frac{1}{4}$, SEC. 4, T. 2 N., R. 32 E. W. M.	REGISTERED PROFESSIONAL LAND SURVEYOR <i>David H. Krumbain</i> OREGON DAVID H. KRUMBEIN 933	RECEIVED BY Umatilla County Surveyor Date <u>6-92</u> Rec'd By <u>KR</u> No. <u>92-48B</u>		