



NARRATIVE

PURPOSE OF THIS SURVEY WAS TO ESTABLISH THE CORNERS OF THE EAST HALF OF THE NORTHWEST QUARTER OF SECTION 10, TOWNSHIP 3 NORTH, RANGE 34 EAST, W.M. AT THE REQUEST OF THE FARM CREDIT SERVICES.

THE SECTION WAS BROKENDOWN FROM THE CORNERS FOUND AS SHOWN. THE NORTHEAST CORNER WAS NOT FOUND AND WAS RESET AT THE INTERSECTION OF TWO ROADS AS CALLED FOR IN THE CO. ROAD DESCRIPTION. THE SOUTHEAST CORNER WAS NOT FOUND BUT WAS REESTABLISHED BY BILL WELLS, P.L.S. IN 1991. USING THE CORNERS 1 SINGLE PROPORTIONED ALL OF THE QUARTER CORNERS IN. THE WEST QUARTER CORNER IS NOT AT THE HALF WAY POINT AS PER THE 1990 SURVEY OF THE DIMINISHED BOUNDARY OF THE RESERVATION.

BEARINGS ARE BASED UPON THE SURVEY BY BILL WELLS FOR INDIAN ALLOTMENT C 340-A FOR THE SOUTH LINE OF SECTION 10. C.S. NO. 92-026B

- INDICATES FOUND CORNER AS NOTED.
 - INDICATES SET 2 1/2 INCH BRASS CAP ON 1 INCH GALVANIZED IRON PIPE.
- (GLO INFORMATION)

KRUMBEIN ENGINEERING LTD. ENGINEERS - SURVEYORS - PLANNERS 361 S.E. Second Pendleton, Oregon	Scale 1" = 500'	Dwn. By HP	Orig. No. 9204C	Revision 1 12-29-92
	Date 5-15-92	Ckd. By DNK	Job No. 9154	Revision 2
BOUNDARY SURVEY FARM CREDIT NW 1/4, SEC. 10, T. 3N, R. 34E W.M.		REGISTERED PROFESSIONAL LAND SURVEYOR David H. Krumbein OREGON DAVID H. KRUMBEIN 925		RECEIVED BY Umatilla County Surveyor Date 10-9-92 Rec'd By KR No. 92-109-B