



## BASIS OF BEARING

True Geodetic North at the quarter corner common to Sections 3 and 10, Township 1 South, Range 34 East of the Willamette Meridian, as established by GPS observation

SCALE: 1" = 300'

## LEGEND

- ⊙ Found 2 1/2" iron pipe with 2 1/2" brass cap, marked as per Umatilla County Monumentation Records
- ⊕ Set 5/8" x 20" iron rebar with 2 1/2" aluminum cap, marked as per Umatilla County Monumentation Records, filed separately
- Set steel fencepost on line
- ( ) Record measurement as per field notes of GLO Special Contract, dated May 4, 1887, executed by James Currin and James Noland

## REFERENCE MATERIAL

Umatilla County Monumentation Records  
 Survey Number 95-205-B  
 Field Notes of GLO Special Contract dated May 4, 1887,  
 executed by James P. Currin and James E. Noland  
 Microfilm Document Number 2013-6120650

## NARRATIVE

This survey was done at the request Patrick Marolla, on behalf of Hancock Forest Management, land manager of the land within. Mr. Marolla wanted the line marked with steel fenceposts prior to a timber harvest. I recover the monuments as shown hereon. I set the sixteenth corner as per BLM Manual of Instruction 2009. Horizontal Datum on geodetic coordinates is NAD83(1991), as was established from Umatilla National Forest control point 'ANDERSON', set by Survey Number 95-205-B. I find no unusual conditions with this survey.

**RECEIVED BY**  
 Umatilla County Surveyor  
 Date: 1/3/2015  
 Rec'd By: G. Hensley  
 No.: 15-003-B



<b>BAGETT, GRIFFITH &amp; BLACKMAN</b> 2006 Adams Avenue, LaGrande, Oregon Map of Survey	
Situate in Section 1, Township 1 South, Range 34 East of the Willamette Meridian	
UMATILLA COUNTY, OREGON	
SURVEYED FOR	Hancock Forest Management
SURVEYED BY	J. S. H.
Scale: 1" = 300'	Drawn by: J. S. H. Dec. 2014