



SCALE 1"=30'



BASIS OF BEARING

BEARING BASE -- CENTERLINE OF SW18TH FROM INTERSECTION WITH SW PERKINS AVENUE NW TO THE FIRST PC ON SW 18TH STREET.

RECORD OF SURVEY

A RECORD OF SURVEY OF CENTERLINE MONUMENTS IN BLAKEY ADDITION AT THE INTERSECTION OF SW 18TH AND SW PERKINS AVENUE, LOCATED IN THE NORTHWEST 1/4 OF THE SOUTHWEST 1/4 OF SECTION 15, TOWNSHIP 2 NORTH, RANGE 32 EAST, WILLAMETTE MERIDIAN, CITY OF PENDLETON, UMATILLA COUNTY, OREGON.

SURVEYOR'S NARRATIVE:

THIS SURVEY WAS PERFORMED AT THE REQUEST OF KEVIN, FROM AMERICAN ROCK PRODUCTS, TO RESET MONUMENTS THAT WERE EITHER HIT OR REMOVED DURING A STREET IMPROVEMENT PROJECT ON S.W. PERKINS AVENUE AND S.W. 18TH STREET, IN BLAKEY ADDITION TO THE CITY OF PENDLETON, WHICH IS LOCATED IN THE NW1/4 OF THE SW1/4 OF SECTION 15, TOWNSHIP 2 NORTH, RANGE 32 EAST, W.M., UMATILLA COUNTY, OREGON. I LOCATED THE CENTERLINE MONUMENTS, AS SHOWN ON THIS DRAWING, AND HOLD THE THREE MONUMENTS CENTERED AROUND THE INTERSECTION OF SW 18TH AND SW PERKINS. I HOLD THE CENTERLINE INTERSECT TO THE MONUMENT TOWARDS THE NORTHWEST, IN SW 18TH STREET, AS A BASELINE AND CHECK INTO THE MONUMENT NORTHEAST OF THE CENTERLINE OF THE INTERSECTION AND CHECKS EXACTLY. I FINE A REBAR IN THE MONUMENT BOX TO THE SOUTHEAST OF THE INTERSECTION, WHICH WAS OFF ABOUT 0.04' (TO THE CENTER OF THE REBAR). I RESET AN ALUMINUM CAP, AND STAMP THE LOCATION POINT ON IT. THIS POINT IS THE PC OF THE CURVE AS IT TRAVELS SOUTHEAST FROM THE INTERSECTION ON SW 18TH STREET. AT THE PT LOCATION I FIND A MONUMENT BOX AND NO MONUMENT. I SET A 5/8" X 24" REBAR (SURVEYOR'S NOTE: THE REBAR WAS DRIVEN TO REFUSAL AND WAS BOUNCING, SO I REMOVED THE REBAR AND CUT IT TO A SHORTER LENGTH). THE REBAR WAS SET, WITH AN ALUMINUM CAP AND THE MARKED THE LOCATION. I USED A SAND MORTAR MIX, UP TO THE CAP, TO STABILIZE BOTH MONUMENTS IN THE MONUMENT BOXES. THIS SURVEY WAS PERFORMED USING A SOKKIA GSR 2700IS RTK GPS SYSTEM. STANDARD ERROR FOR THE RTK SYSTEM IS 10.0MM + 1 PPM X BASELINE MEASURED, IN MILLIMETERS. I FIND NOTHING OUT OF THE ORDINARY ON THIS SURVEY.

Robert D. English

ROBERT D. ENGLISH, WAPLS44338

REFERENCES:

- (R1) BLAKEY ADDITION PLAT BOOK II, PAGE 18, KRUMBEIN, TO THE CITY OF PENDLETON, OR. 1977.
- (R2) COUNTY SURVEY NO. 98-14-A, HARRIS FOR SCHUMACHER, 1997.

RECEIVED BY

Umatilla County Surveyor
Date: 8/6/20
Rec'd By: CT
No.: 20-067-6

LEGEND

- FOUND 5/8" IRON REBAR WITH ALUMINUM CAP, OR AS NOTED.
- SET 5/8"X24" IRON REBAR IN EXISTING MON BOX, WITH 2"ALC
- XXX(R#) RECORD AND REFERENCE TO PLAT
- CENTERLINE OF ORIGINAL PLAT

REGISTERED PROFESSIONAL LAND SURVEYOR
Robert D. English
OREGON
JANUARY 11, 2005
ROBERT DOUGLAS ENGLISH
434061.S
RENEWAL DATE: 12/31/21

| | | |
|-----------------------------------|------------------------|---|
| DATE: 07/28/20 | DWN.BY: RDE | RECORD OF SURVEY FOR: CITY OF PENDLETON |
| SCALE: 1"=30' | CHK. BY: RDE | SW 18TH AND SW PERKINS AVENUE PENDLETON, OR 97801 |
| JOB NO. 2020-046 | REV. DATE: XX/XX/XX | SURVEY ONE, LLC |
| DWG NO. AMROCKSW18THPERKIN.DWG | | P.O. BOX 382 PENDLETON OR, 97801 PH:541-276-2055 FAX:541-276-3480 |

