



C. H. Storms & Associates
 CONSULTING ENGINEERS
 304 DENNY BUILDING TELEPHONE 4170 WALLA WALLA, WASH.

Structural	A SURVEY FOR	
Hydraulic	MABLE HARRIS	
Sanitary	IN N/2 SECTION 20	
Designs	T 5 N 12 36 E 10 M.	
Land Surveys	Date	9/13/48
House Plans	Drawn By	V. O. B.
Blue Prints	Checked By	CHS
Estimates	5036 20-21	650

SHEET 1 OF 1

Q-809-B 1165

City Pl
Supervi^a
Valu^{on}
Sur^{eying}
r^{ports}
Designs

C. H. Storms & Associates

CONSULTING ENGINEERS

REGISTERED WASHINGTON, OREGON

C. H. STORMS
Phone 4692-W

G. M. NEWBILL
Phone 2982-M

GEO. LAUBACK
B. F. CHAPMAN
J. O. BICKFORD, Jr.
E. BUCKNER

TELEPHONE 4170
304 Denny Building
WALLA WALLA, WASH.

FILE

FIELD NOTES

OWNER: Mabel Harris

TYPE OF SURVEY: Boundary

LOCATION: Section 20, Township 5 North, Range 36 EWM

Beginning at the Northwest corner of Section 20, Township 5 North, Range 36 EWM, which is marked by a stone with a cross, I ran South $00^{\circ}40'$ East to the Southwest corner of said Section a distance of 5,340.50 feet and found a stone with a wagon skein. I ran thence $N88^{\circ}37'$ E. a distance of 5,316.30 feet to the Southeast corner of said Section marked by a 2" pipe. I ran thence $N. 00^{\circ}54'$ W. a distance of 2,641.50 feet to the East one-quarter corner of said section marked by a stone. I continued thence $N. 00^{\circ}54'$ W. a distance of 2,571.30 feet to the Northeast corner of said Section marked by a locust post. I ran West 5,295.04 feet to the point of beginning. From this information, I laid out the property shown on the accompanying plat by proportional measurements.

Cecil H. Storms

C. H. Storms
Professional Engineer
Reg. No. 2512