

R-132-B

NARRATIVE OF SURVEY

Survey For: Schroederbuilt, Inc., Athena, Oregon

Location of Survey: Lot 9 and the East $\frac{1}{2}$ of Lot 10, Block 2 of Kirk's Addition to Athena located in the NW $\frac{1}{4}$ of Section 19, Township 4 North, Range 35 East, W.M., Umatilla County, Oregon.

Method and Procedure: Kirk's Addition was originally platted in 1879 and I could find no subsequent re-surveys of Block 2, Kirk's Addition in the County Records. The monuments set were based on proportionate measure from evidence found at Main and Second Street, Main and Third Street, College and Second Street, as shown on map number P-125-A in the Umatilla County Surveyors Office, and a pin found on the Southerly right-of-way of College Street, 190 feet East of the centerline of Fifth Street as shown on map number Q-1077-AX in the Umatilla County Surveyor's Office.

Angles were measured with a 1 second theodolite and distances were measured with infra-red distance measuring equipment and a 300 foot steel tape. Bearings were based on the centerline of Second Street being due North.

This survey was done June 24, 1980.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

William R. Wells
William R. Wells, PLS
Wallulis and Associates, Inc.
P.O. Box 398
Pendleton, Oregon 97801
July 1, 1980