



LOCAL DATUM COORDINATES		
STATION	NORTHING	EASTING
131+78.46 C	19,865.67	6822.91
131+78.46 N.W. R/W PIN	19,898.61	6788.56
131+78.46 S.W. R/W PIN	19,832.61	6788.45
140+76.70 C	19,864.12	5924.67
140+76.70, 33' LT	19,831.12	5924.70
140+76.70, 33' RT	19,897.12	5924.63
149+32.96 C	19,863.61	5068.41
149+32.96, 33' LT	19,830.61	5068.40
149+32.96, 33' RT	19,896.61	5068.43
158+35.70 (1/4 COR 8/17) C	19,864.93	4165.68
158+35.70, 33' LT	19,831.93	4165.75
158+35.70, 33' RT	19,897.93	4165.61
SEC. COR. 8/9 17/16	19,879.67	6818.43
SEC. COR. 9/10 16/15	19,965.04	12,046.73

**LEGAL DESCRIPTION - UNIT "B"**

A STRIP OF LAND FOR ROAD PURPOSES LOCATED IN THE SOUTHEAST 1/4 OF SECTION 8, TOWNSHIP 4 NORTH, RANGE 29 E.W.M., AND THE NORTHEAST 1/4 OF SECTION 17, TOWNSHIP 4 NORTH, RANGE 29 E.W.M., BEING 66 FEET IN WIDTH AND LYING 33 FEET ON EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE:  
 COMMENCING AT A BRASS-CAPPED MONUMENT MARKING THE CORNER COMMON TO SECTIONS 8, 9, 17, AND 16, TOWNSHIP 4 NORTH, RANGE 29 E.W.M.; THENCE S 17° 44' 41" E, 14.70 FEET TO A RAILROAD SPIKE SET IN THE INTERSECTION OF EAST HIGHLAND EXTENSION (CO. RD. #1198) AND SOUTH EDWARDS ROAD (CO. RD. #1201) AND THE TRUE POINT, OF BEGINNING OF THIS DESCRIPTION; THENCE S 89° 54' 05" W, 898.24 FEET; THENCE S 89° 57' 57" W, 856.26 FEET; THENCE N 89° 54' 58" W, 902.73 FEET, TO A BRASS-CAPPED MONUMENT MARKING THE 1/4 CORNER COMMON TO SECTIONS 8 AND 17, TOWNSHIP 4 NORTH, RANGE 29 E.W.M. AND THERE TERMINATING.

**NARRATIVE OF SURVEY**

THE PURPOSE OF THIS SURVEY WAS TO MONUMENT THE PORTION OF EAST HIGHLAND EXTENSION FROM SOUTH EDWARDS ROAD WESTERLY TO THE 1/4 CORNER COMMON TO SECTIONS 8 AND 17, TOWNSHIP 4 NORTH, RANGE 29 EAST WILLAMETTE MERIDIAN AFTER THE UMATILLA COUNTY REMONUMENTATION SURVEY #95-59-B BY EDWARDS SHOWED THE ROAD TO BE SHIFTED OFF OF THE SECTION LINE. MONUMENTS WERE SET AT ALL CENTERLINE ANGLE POINTS, BUT SOME WERE NOT SET ON THE RIGHT-OF-WAY LINES, AS THEIR POSITIONS FELL IN CULTIVATED LAND. THE BEARING BASE USED WAS THE NORTH LINE OF SECTION 16 BEING S 89° 03' 52" W FROM C.S. #95-59-B AS SHOWN. INSTRUMENTS USED WERE A WILD T-16 ONE MINUTE THEODOLITE AND A WILD D1-5 E.D.M. THE CLOSED TRAVERSE USED WAS ADJUSTED BY THE COMPASS RULE.

**LEGEND**

- ✚ FOUND SECTION CORNER AS NOTED
- ⊕ FOUND 1/4 OR 1/16TH CORNER AS NOTED
- ⊙ CALCULATED POINT -NOT SET
- SET 5/8" X 30" IRON PIN WITH PLASTIC CAP MARKED "UMA. CO. RD. DEPT. ... LS 2627"
- ⊠ TELEPHONE PEDESTAL
- POWER POLE
- △ SET RR SPIKE W/PUNCH MARK STAMPED "LS 2627"
- IRRIGATION BURIED
- ⊞ MAIL BOX
- RIGHT-OF-WAY LINE
- CENTERLINE
- EDGE OF PAVEMENT OR GRAVEL

REGISTERED PROFESSIONAL LAND SURVEYOR  
 JULY 28, 1993  
 GARY R. ROBERTS  
 2627  
 RENEWS 12-31-98

UMATILLA COUNTY ROAD DEPT 3920 Westgate Pendleton, Oregon 97801		
Survey for: Legalization of County Road #1198 Unit "B"		
Located: SE 1/4 of Section 8 and NE 1/4 of Sec. 17, Township 4 North, Range 29 E.W.M.		
Survey By: Gary Roberts	Drawn By: Jeanne Gorham	Checked By: Gary Roberts
Scale: 1" = 100'	Date: May, 1996	Sheet: 1 of 1

12-96  
 KK  
 96-183-C