

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 1421
 "STANFIELD EAST BASE 1916 1941"
 QUARTER SECTION: NE GEODETIC COOR: NAD 83(91)
 SEC. 3 TWP.3 N,RGE.28E LAT: 45°46'17.27262" N
 UMATILLA CO.ORE.
 DATE SET: JULY ,1993 LONG: 119°17'51.55703" W
 SURVEYOR: WALTER L. CASWELL SP. COOR: NAD 83(91)
 PLS 737 N: 769651.379 INT.FT.
 FIRM: EAGLE GPS SURVEY CORP E: 8508898.291 INT.FT.
 13545 NW SCIENCE PARK DR
 PORTLAND, OR. 97229 THETA: 0°51'09.671"
 (503) 643-1073
 TYPE: GPS SCALE FACTOR: 0.999949926
 ORDER: B ELEV: 755.195 US.FT.
 ELEV. DATUM: NGVD 29

 DIRECTIONS "TO REACH"

FROM THE INTERSECTION OF COE AVE. AND MAIN STREET IN STANFIELD,
 TRAVEL WEST ON COE AVE. 0.25 MILE TO JOHNSON ST. GO SOUTHWEST ON
 JOHNSON ST. AND THEN WEST ON UMATILLA MEADOWS ROAD A TOTAL OF 0.8
 MILE TO A CROSSROAD TO THE SOUTH. TRAVEL SOUTH ON SAID CROSSROAD
 1 MILE (OVER I-84) TO EMIGRANT BUTTE ROAD. TRAVEL WEST ON
 EMIGRANT BUTTE ROAD 2.6 MILES TO A FORK AND GATE TO THE RIGHT.
 PASS THROUGH GATE AND GO N.W. ON SAND ROAD FOR 0.25 MILE TO A
 FORK. TAKE THE LEFT FORK AND GO WEST 0.3 MI. TO AN OLD FENCE
 (ONLY WOOD POSTS REMAINING). TRAVEL NORTHERLY ALONG LINE OF
 FENCE POSTS TO THE CORNER (0.2 MI). TRAVEL NORTHEASTERLY TOWARDS
 THE TOP OF THE FIRST PEAK 0.2 MILE TO MONUMENT IN 1' SQUARE
 CONCRETE BOX. (ALSO 2 R.M. EXIST).

STATION IS A 3" DIAMETER BRASS DISK, U.S. ARMY CORPS OF ENGINEERS
 STAMPED "STANFIELD EAST BASE USC & GS 1941 1916".

METERS X 3.28083333333 = U.S. FEET
 METERS X 3.28083989501 = INTERNATIONAL FT.



Exp. 12/31/93