

HORIZONTAL CONTROL DATA

OREGON STATE PLANE, NORTH ZONE (3601)

STA. NAME: 9323

QUARTER SECTION: SE

GEODETIC COOR: NAD 83(91)

SEC. 9 TWP.4 N,RGE.28E
UMATILLA CO.ORE.

LAT: 45°50'06.25960" N

DATE SET: JULY ,1993

LONG: 119°19'00.93156" W

SURVEYOR: WALTER L. CASWELL
PLS 737

SP. COOR: NAD 83(91)

FIRM: EAGLE GPS SURVEY CORP
13545 NW SCIENCE PARK DR
PORTLAND, OR. 97229
(503) 643-1073

N: 792770.201 INT.FT.

E: 8503641.771 INT.FT.

THETA: 0°50'20.471"

TYPE: GPS

SCALE FACTOR: 0.999962250

ORDER: SECOND, CLASS: 1

ELEV: 487.299 US.FT.

ELEV. DATUM: NGVD 29

DIRECTIONS "TO REACH"

FROM THE INTERSECTION OF HIGHLAND AVE. AND HWY. 207, TRAVEL WEST ON HIGHLAND AVE. 0.25 MILE. (LOOK FOR CONVENIENCE STORE ON NORTH SIDE OF ROAD). MONUMENT IS SOUTH OF THE CENTERLINE OF HIGHLAND ROAD 30 FEET.

STATION IS A 5/8" X 30" IRON ROD WITH A YELLOW PLASTIC CAP INSCRIBED "BUFORD ASSOC. PLS 1148".

STATION IS 30 FEET SOUTH OF CENTERLINE OF HIGHLAND ROAD, 75 FEET EAST AND 18 FEET SOUTH OF POWER POLE NO. 4N 8E, 167901.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Walter L. Caswell

OREGON
JULY 8, 1966
WALTER L. CASWELL
737

EXP. 12/31/93

METERS X 3.28083333333 = U.S. FEET
METERS X 3.28083989501 = INTERNATIONAL FT.