

Bonneville Power Administration  
Geodetic Control Data Sheet

Station: WM046 (246)  
Project: Wallula-Smiths Harbor-McNary  
Section: NE 1/4 27 Township: 5 North Range: 29 East Meridian: Willamette  
County: Umatilla State: OR USGS Quad: Hat Rock, Oregon  
Surveyor: M R Heidecke Date Surveyed: July, 2001

Instrument:

The horizontal coordinates and orthometric elevation were established by GPS observations using six Trimble 4000 SSI dual frequency receivers with Compact L1/L2 antennae with ground plane.

Adjustment:

The Basis of Coordinates for this survey is the Oregon State Coordinate System, North Zone, NAD 83 (1998). The horizontal component of the least squares adjustment was constrained by holding NGS Stations B 340 (A), B 502 (B), PENDLETON (B), STANFIELD EAST BASE RESET (B), and BURDEN (B). The vertical component of the least squares adjustment was constrained by holding NGS Benchmarks B 340 (First Order Class II), B 502 (First Order Class II), BURDEN (Second Order Class II), V 203 (Second Order Class 0), G 640 (First Order Class I). The elevation for point 106, 201, 249, and 255 were determined by differential leveling from G 640, D 502, E 525 and F 431 respectively and held.

Horizontal Datum: NAD83 (1998) Linear Unit: International Feet  
Vertical Datum: NAVD88 Linear Unit: U.S. Survey Feet

Latitude: <u>N 45-53-34.76750</u>	Longitude: <u>W 119-10-15.23720</u>
US State Plane Coordinate System: <u>Oregon North Zone - 3601</u>	
Northing: <u>814,466.080</u>	Easting: <u>8,540,510.324</u>
Orthometric Elevation: <u>492.89</u>	Ellipsoid Height: <u>421.79</u>
Combined Factor: <u>0.99995443</u>	Convergence: <u>- 0-56-33</u>
Confidence: 95% Confidence ("1.96 Sigma") Values	
<u>Northing-0.010</u>	<u>Easting-0.008</u>
	<u>Elevation-0.108</u>

Monumentation: BPA 3/4-inch Aluminum Cap on 5/8-inch aluminum rod, flush with ground.  
Stamping: U.S.D.O.E. Bonneville Pwr. Adm., WM046 - FEC-01 - ATB - GPS

To-Reach Description:

Begin at Umatilla Post Office, Umatilla, OR. 97882. Drive east on Highway 730, 7.5 miles to intersection of State Highway #207 to the right (south). Drive southwesterly on State Highway #207 0.8 miles to the intersection of East Progress Road. Drive east on East Progress Road 0.4 miles to gate and sign "Private Road". Continue east on East Progress Road 0.2 miles to end of pavement and station on south side of the road. Station is 122 feet southeast from road centerline at end of pavement.

Witness post is a yellow carsonite marker inscribed with BPA logo, bearing and distance to station.

RECEIVED BY

Umatilla County Surveyors

Date

Rec'd By

02-19-01

