

5N35D25

TOMKINS LAND SURVEYING, INC.  
20 EAST POPLAR, SUITE 204  
WALLA WALLA WA 99362  
PHONE: 509/522-4843  
FAX 509/522-1902  
email: tomkins@wwics.com

JUNE 17, 1998

**HORIZONTAL CONTROL DATA**

STA. NAME: 1048

LOCATION: TOWNSHIP 5 NORTH, RANGE 35 EAST, WILLAMETTE MERIDIAN. SOUTHEAST 1/16 CORNER OF SECTION 1.

DESCRIPTION: BRASS CAP IN A MONUMENT CASE IN THE CENTER OF THE NORTH BOUND LANES OF HIGHWAY 11 70± NORTH OF MAIN STREET.

GEODETIC COORDINATE: NAD 83(91)

LAT: 45°55'58.94278" N.

LONG: 118°23'15.41116" W.

STATE PLANE COORDINATE: NAD 83(91) OREGON NORTH ZONE (3601)

N: 253993.714 METERS

E: 2663808.304 METERS

N: 833312.710 INT. FEET

E: 8739528.540 INT. FEET

ELEVATION: 317.46 METERS

1041.55 FEET

ELEVATION DATUM: NAVD 88

THETA: 1°29'53.1"

GRID FACTOR: 0.999983664

SEA LEVEL FACTOR: 0.999950182

COMBINED SCALE FACTOR: 0.999933847

**CONVERSION:**

METERS X 3.28083333333 = U.S. FEET

METERS X 3.28083989501 = INTERNATIONAL FEET

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Greg E. Flowers*

OREGON  
JUNE 30, 1997  
GREG E. FLOWERS  
02820LS

RENEWS 12/31/99

6/17/98