

5N35 E25

TOMKINS LAND SURVEYING, INC.
20 EAST POPLAR, SUITE 204
WALLA WALLA WA 99362
PHONE: 509/522-4843
FAX 509/522-1902
email: tomkins@wwics.com

JUNE 17, 1998

HORIZONTAL CONTROL DATA

STA. NAME: 1023

LOCATION: TOWNSHIP 5 NORTH, RANGE 35 EAST, WILLAMETTE MERIDIAN. N.E. CORNER OF SECTION 12..

DESCRIPTION: 2 1/2" BRASS CAP 5" BELOW THE SURFACE AT THE ROAD CENTERLINE INTERSECTION AT THE N.E. CORNER OF THE IOOF CEMETARY.

GEODETIC COORDINATE: NAD 83(91)

LAT: 45°55'58.83761" N.

LONG: 118°22'19.19077" W.

STATE PLANE COORDINATE: NAD 83(91) OREGON NORTH ZONE (3601)

N: 254022.249 METERS

E: 2665019.138 METERS

N: 833406.329 INT. FEET

E: 8743501.120 INT. FEET

ELEVATION: 358.79 METERS

1177.14 FEET

ELEVATION DATUM: NAVD 88

THETA: 1°30'32.9"

GRID FACTOR: 0.999983657

SEA LEVEL FACTOR: 0.999943697

COMBINED SCALE FACTOR: 0.999927355

CONVERSION:

METERS X 3.28083333333 = U.S. FEET

METERS X 3.28083989501 = INTERNATIONAL FEET

<p>REGISTERED PROFESSIONAL LAND SURVEYOR</p> <p><i>Greg E. Flowers</i></p> <p>OREGON JUNE 30, 1997 GREG E. FLOWERS 02820LS</p>
--

RENEWS 12/31/99

6/17/98