

5N35 E 24

TOMKINS LAND SURVEYING, INC.  
20 EAST POPLAR, SUITE 204  
WALLA WALLA WA 99362  
PHONE: 509/522-4843  
FAX 509/522-1902  
email: tomkins@wwics.com

JUNE 17, 1998

**HORIZONTAL CONTROL DATA**

STA. NAME: 923

LOCATION: TOWNSHIP 5 NORTH, RANGE 35 EAST, WILLAMETTE MERIDIAN. WEST 1/4 CORNER OF SECTION 24.

DESCRIPTION: 2 GALVANIZED IRON PIPE IN A NORTH-SOUTH FENCE LINE, PROTRUDING 24" ABOVE THE GROUND, 1000± WEST OF STATE HIGHWAY 11.

GEODETIC COORDINATE: NAD 83(91)

LAT: 45°53'46.47760" N.

LONG: 118°23'31.71998" W.

STATE PLANE COORDINATE: NAD 83(91) OREGON NORTH ZONE (3601)

N: 249896.165 METERS

E: 2663563.771 METERS

N: 819869.308 INT. FEET

E: 8738726.280 INT. FEET

ELEVATION: 448.19 METERS

1470.46 FEET

ELEVATION DATUM: NAVD 88

THETA: 1°29'41.5"

GRID FACTOR: 0.999975275

SEA LEVEL FACTOR: 0.999929668

COMBINED SCALE FACTOR: 0.999904945

**CONVERSION:**

METERS X 3.28083333333 = U.S. FEET

METERS X 3.28083989501 = INTERNATIONAL FEET

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Greg E. Flowers*

OREGON  
JUNE 30, 1997  
GREG E. FLOWERS  
02820LS

RENEWS 12/31/99

6/17/98