

TOMKINS LAND SURVEYING, INC.  
20 EAST POPLAR, SUITE 204  
WALLA WALLA WA 99362  
PHONE: 509/522-4843  
FAX 509/522-1902  
email: tomkins@wwics.com

JUNE 17, 1998

**HORIZONTAL CONTROL DATA**

STA. NAME: 908

LOCATION: TOWNSHIP 6 NORTH, RANGE 35 EAST, WILLAMETTE MERIDIAN. 1/4 CORNER  
COMMON TO SECTIONS 34 & 35.

DESCRIPTION: 5/8" REBAR WITH A YELLOW PLASTIC CAP STAMPED "TOMKINS SURVEYING", SET  
10' EAST OF THE EAST EDGE OF WINESAP ROAD NEAR THE EASTERLY PROJECTION OF THE  
SOUTHERLY RIGHT-OF-WAY LINE OF YELLOW JACKET ROAD..

GEODETIC COORDINATE: NAD 83(91)

LAT: 45°57'17.05225" N.

LONG: 118°24'47.25692" W.

STATE PLANE COORDINATE: NAD 83(91) OREGON NORTH ZONE (3601)

N: 256353.095 METERS

E: 2661768.037 METERS

N: 841053.461 INT. FEET

E: 8732834.780 INT. FEET

ELEVATION: 280.38 METERS

919.87 FEET

ELEVATION DATUM: NAVD 88

THETA: 1°28'47.9"

GRID FACTOR: 0.999988806

SEA LEVEL FACTOR: 0.999956002

COMBINED SCALE FACTOR: 0.999944808

**CONVERSION:**

METERS X 3.28083333333 = U.S. FEET

METERS X 3.28083989501 = INTERNATIONAL FEET

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Greg E. Flowers*

OREGON  
JUNE 30, 1997  
GREG E. FLOWERS  
02820LS

RENEWS 12/31/99

6/17/98