

TOMKINS LAND SURVEYING, INC.
20 EAST POPLAR, SUITE 204
WALLA WALLA WA 99362
PHONE: 509/522-4843
FAX 509/522-1902
email: tomkins@wwics.com

JUNE 17, 1998

HORIZONTAL CONTROL DATA

STA. NAME: 903

LOCATION: TOWNSHIP 6 NORTH, RANGE 35 EAST, WILLAMETTE MERIDIAN. N.W. 1/4 OF SECTION 36.

DESCRIPTION: ½" REBAR WITH A RED PLASTIC CAP STAMPED "TOMKINS CONTROL", 300± WEST OF STATE HIGHWAY NO. 11, 10' WEST OF AN IRRIGATION DITCH ON THE EAST EDGE OF AN ORCHARD, NEAR THE N.W. CORNER OF A TRAILER PARK.

GEODETIC COORDINATE: NAD 83(91)

LAT: 45°57'11.38559" N.

LONG: 118°23'19.20999" W.

STATE PLANE COORDINATE: NAD 83(91) OREGON NORTH ZONE (3601)

N: 256227.456 METERS

E: 2663668.049 METERS

N: 840641.260 INT. FEET

E: 8739068.410 INT. FEET

ELEVATION: 293.65 METERS

963.43 FEET

ELEVATION DATUM: NAVD 88

THETA: 1°29'50.4"

GRID FACTOR: 0.999988428

SEA LEVEL FACTOR: 0.999953918

COMBINED SCALE FACTOR: 0.999942347

CONVERSION:

METERS X 3.28083333333 = U.S. FEET

METERS X 3.28083989501 = INTERNATIONAL FEET

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Greg E. Flowers

OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/99

6/17/98