

TOMKINS LAND SURVEYING, INC.
20 EAST POPLAR, SUITE 204
WALLA WALLA WA 99362
PHONE: 509/522-4843
FAX 509/522-1902
email: tomkins@wwics.com

JUNE 17, 1998

HORIZONTAL CONTROL DATA

STA. NAME: 904

LOCATION: TOWNSHIP 6 NORTH, RANGE 35 EAST, WILLAMETTE MERIDIAN. N.E. 1/4 OF SECTION 36.

DESCRIPTION: 5/8" REBAR WITH A YELLOW PLASTIC CAP STAMPED "TOMKINS SURVEYING" 30' WEST OF EASTSIDE ROAD AND 20' SOUTH OF A DRIVEWAY. NEAR THE N.E. CORNER OF AN ORCHARD.

GEODETIC COORDINATE: NAD 83(91)

LAT: 45°57'10.49765" N.

LONG: 118°22'55.58787" W.

STATE PLANE COORDINATE: NAD 83(91) OREGON NORTH ZONE (3601)

N: 256213.364 METERS

E: 2664177.307 METERS

N: 840595.026 INT. FEET

E: 8740739.210 INT. FEET

ELEVATION: 293.19 METERS

961.91 FEET

ELEVATION DATUM: NAVD 88

THETA: 1°30'07.1"

GRID FACTOR: 0.999988369

SEA LEVEL FACTOR: 0.999953991

COMBINED SCALE FACTOR: 0.999942360

CONVERSION:

METERS X 3.28083333333 = U.S. FEET

METERS X 3.28083989501 = INTERNATIONAL FEET

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Greg E. Flowers
OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/99

6/17/98