

OREGON CORNER RESTORATION FORM

T1N R31E A25

Section 1, Township 1N, Range 31E,
County Umatilla, Date November 15, 2004.

- Condition Report
- Not Found
- Remonumented
- Unrecorded
- Surveyed in
- Referenced out

Township corner common to Townships 1 and 2 North
Ranges 31 and 32 East, W.M., Umatilla County, Oregon.

Previous Renewals / Surveys, etc.


The corner was originally set by Josiah A. Burnett under Contract No. 92 dated September 12, 1860. His record Reads: Set post and drove charred stake, raised mound with trench as per instructions. Surveyor Bill Wells, under County Survey 93-54-C found the remains of a charred stake 18" below the surface at the intersection of old fences. He held the fence intersection as the best available evidence. His record reads: Set a 2 1/2" brass cap on a 1 1/4" x 30" galv. iron pipe, 27 inches in the ground with a mound of stone to the cap. See his filed corner certificate for calls to his reference objects.

Monument and accessories found: (Condition and source)

I found the brass cap set by Wells in the mound in good condition. The fence corner has been burned but is still standing. The fences are no longer maintained since the adjacent fields are in CRP. I did not tie his references.

DIAGRAM

SKETCH



Monument and accessories set: (Procedures and description)

None.

Location and Comments
SPC Oregon North, NAD 83-91
Northing = 709,945.04 ift
Easting = 8,618,848.52 ift

Compass Declination

Surveyor's Seal

Witnessed By:
RECEIVED BY:
Umatilla County Surveyor
Date: 5-05
Rec'd By: KK
No. 05-111-C

Firm / Agency
Witness Tree Surveying
P.O. Box G
Pilot Rock, OR 97868
Party Chief
Stephen K. Haddock, PLS

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Stephen K. Haddock
OREGON
JULY 9, 2001
STEPHEN K. HADDOCK
56295LS

RENEWAL DATE 6-30-05