

**OREGON CORNER RESTORATION FORM**

Section 3 Township 1N Range 32E  
County Umatilla Date: April 1, 2009

Corner Designation: 1N32E17

Corner common to sections 2, 3, 10, and 11,  
T1N, R32E, W.M., Umatilla County, Oregon.

Previous Renewals / Surveys, etc.


Corner was originally set by Daniel Chaplin under contract No. 107 dated September 21, 1864. His record reads: Set stone, 20 x 16 x 8, for corner to secs. 2, 3, 10 and 11. Zenas F. Moody under contract No. 164, dated October 4, 1871, stated: Set stone, 18 x 16 x 10. Currin and Noland under special contract dated May 4, 1887, stated: Set stone 8 x 10 x 12 ins. J. Kimbrell in survey in Book 2, Page 32, stated: Set stone. Donald L. Staebler in survey F-11-B states: Found brass cap now underwater.

Condition Report Only  
 Not found  
 Remonumented  
 Unrecorded  
 Surveyed in  
 Referenced out

Monument and Accessories found: ( condition and source )

None. This point falls in what is currently the deepest part of McKay Reservoir.

**DIAGRAM**



**SKETCH**

**MONUMENT (S) AND ACCESSORIES SET (Procedures and Description)**

None. I calculated the position from ties to the Rancho Vista Addition monuments. This certificate is being recorded to report the state plane coordinates for the corner point given below.

For references,

Location and comments  
NAD 83/1991 State Plane Coordinate  
Oregon North Zone  
N = 704,915.32 ift  
E = 8,640,651.95 ift

Compass Declination

Surveyors Seal

RECEIVED BY:  
Umatilla County Surveyor  
Date: 6-10  
Rec'd By: KK  
No. 10-93C

Firm / Agency  
Witness Tree Surveying  
Address  
P.O. Box G  
Pilot Rock, Or. 97868  
Party Chief  
Stephen K, Haddock

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Stephen K. Haddock*

OREGON  
JULY 9, 2001  
STEPHEN K. HADDOCK  
56295LS

RENEWAL DATE 6-30-11