

**OREGON CORNER RESTORATION FORM**

Section 10 Township 1N Range 32E  
County Umatilla Date: July 6, 2009

Corner Designation: 1N32G17  Condition Report Only  
Not found  
Remonumented  
Unrecorded  
Surveyed in  
Referenced out


Quarter corner common to sections 10 and 11,  
T1N, R32E, W.M., Umatilla County, Oregon.

Previous Renewals / Surveys, etc.

Corner originally set by Daniel Chaplin under contract No. 107 Dated September 21, 1864.  
His record reads: Set post for 1/4 section corner in mound of earth with charred stake,  
pits, etc., as per instructions. Zenas F. Moody under contract No. 164 dated October 4, 1871  
states: Set post. Currin and Noland under special contract dated May 4, 1887 state: Set stone  
7 x 8 x 9 ins., 6 ins. in the ground. L.E. Wilkes in 1917 set a brass cap witness corner 1lk south  
of the true corner. Survey H-250-B states: Found original stone 9x8x7. David H. Krumbein in  
record of survey 03-232-B states: Found rock. David L. Haddock in record of survey 05-100-B  
states: Found stone and brass cap witness corner.

Monument and Accessories found: ( condition and source )  
I found the stone by Currin and the brass cap by Wilkes in good condition.

**DIAGRAM**



**SKETCH**

**MONUMENT (S) AND ACCESSORIES SET (Procedures and Description)**

I made no modification to the monument or accessories. This purpose of this certificate is to  
report the state plane coordinates of the corner point. The coordinate given is of the true corner  
point and not the witness monument by Wilkes.

For references:

This monument was tied using a Trimble R7/R8 RTK GPS system.

Location and comments  
NAD 83/1991 State Plane Coordinate  
Oregon North Zone  
N = 702,291.49 ift  
E = 8,640,700.89 ift

Compass Declination

Surveyors Seal

RECEIVED BY:  
Umatilla County Surveyor  
Date: 6-10  
Rec'd By: KH  
No. 10-93-C

Firm / Agency  
Witness Tree Surveying  
Address  
P.O. Box G  
Pilot Rock, OR 97868  
Party Chief  
Stephen K, Haddock

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Stephen K. Haddock*

OREGON  
JULY 9, 2001  
STEPHEN K. HADDOCK  
56295LS

RENEWAL DATE 6-30-11