

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 8/12/96

CORNER DESIGNATION: J-13. Southeast corner Section 9, T1N., R32E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner originally established by Daniel Chaplin under Contract No. 107, dated September 21, 1864. Surveyor General records state: Set post for corner to secs. 9, 10, 15 and 16 in mound of earth with charred stake, pits &c as per instructions.

MONUMENT AND ACCESSORIES FOUND: Fence intersection, which agrees with improvements and tie to corner shown on railroad maps.

**MONUMENT MARKING DETAIL:**

T1N R32E  
S9 | S10  
-----  
S16 | S15  
1996  
ORLS 1106

MONUMENT SET: At position determined by old wood hub at fence corner, set a 2 1/2 in. brass cap on a 1 in. x 30 in. galvanized iron pipe, projecting 2 in. out of the ground. (marked as shown in the monument detail).

**New Accessories:**

A Pacific Power and Light Pole #099000 bears South 82° East - 196.5 feet, to brass washer nailed to pole.  
A 7 in. x 9 in. railroad tie gate post bears South 41 1/2° West - 140.7 feet, to brass washer nailed to pole.  
A 9 in. diameter pole fence corner post bears South 77 1/2° West - 88.3 feet, to brass washer nailed to pole.  
A 7 in. x 9 in. railroad tie gate post bears North 61 1/4° East - 51.7 feet, to brass washer nailed to pole.  
All new accessories have bearing object signs attached.  
A survey monument sign is attached to the fence corner post alongside the brass cap monument. Brass washers are stamped "PLS 1106".

**LOCATION & COMMENTS:**

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

Witness: William L. Hanley, PLS  
Kelly Snively

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-98*

**RECEIVED BY**

Umatilla County Surveyor  
Date 10-96  
By JK  
No. 96-1678