

OREGON CORNER RESTORATION FORM

Section 36 Township 1N Range 32E
County Umatilla Date: June 29, 2009

Corner Designation: 1N32Z25 Condition Report Only
Not found
Remonumented
Unrecorded
Surveyed in
Referenced out


Corner to Township 1 North, Ranges 32 and 33 East,
Section 36, T1N, R32E and Section 31 T1N, R33E,
W.M., Umatilla County, Oregon.

Previous Renewals / Surveys, etc.

Corner originally set by David P. Thompson under contract No. 79, dated July 26, 1858. His record reads: Set post for corner to Townships 1 North, Ranges 32 and 33 East. James Currin and James Noland under Special Instructions dated May 4, 1887 state: Set basalt stone, 16x14x10 marked SC with 6 notches on N., E. and W. edges. and raised mound of stone. Lincoln Wilkes in the 1917 survey for the Diminished Indian Reservation states: set an iron post, 3 ft. long, 2 ins. diam., with brass cap. Ron Scherler in a 1976 dependent resurvey states: Found a 2" iron post with brass cap with the section numbers reversed. Re-marked as shown.

Monument and Accessories found: (condition and source)
I found the Wilkes monument in good condition, marked as indicated by Scherler.

DIAGRAM



SKETCH

MONUMENT (S) AND ACCESSORIES SET (Procedures and Description)
None.

This monument was tied to report the Oregon State Plane, NAD 83/1991 coordinates only.

Measurements were made with a Trimble R7/R8 RTK GPS system.

Location and comments
NAD 83/1991 State Plane Coordinate
Oregon North Zone
N = 678,749.88 ift
E = 8,651,725.27 ift

Compass Declination

Surveyors Seal

RECEIVED BY:
Umatilla County Surveyor
Date: 6-10
Rec'd By: KK
No. 10-98-C

Firm / Agency
Witness Tree Surveying
Address
P.O. Box G
Pilot Rock, OR 97868
Party Chief
Stephen K, Haddock

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Stephen K. Haddock

OREGON
JULY 9, 2001
STEPHEN K. HADDOCK
56295LS

RENEWAL DATE 6-30-11