

PUBLIC LAND CORNER CONDITION REPORT

UMATILLA COUNTY, DATE: 01/23/02

CORNER DESIGNATION: 2N33Z17, the Southeast corner of Section 34.

PREVIOUS RENEWALS/ SURVEYS, ETC..:

Most recent Umatilla County Surveyors recorded survey record: I-176-A and BLM survey No. R651.

MONUMENT AND ACCESSORIES FOUND:

Found a 2 1/2" brass cap on iron pipe monument with top 10" above ground level, marked as shown in monument marking detail. This is a witness corner 20 feet North of true corner point. Found monument at true corner point, a 3" brass cap, on stainless steel pipe, with cap 4" above ground level, at West side of a mound of stones, with steel fence post 1.0 feet North, marked as shown in monument marking detail.

MONUMENT MARKING DETAIL:

INDIAN ALLOTMENT

T2N

S34 | S35

S3 | S2

T1N R33E

WC 20 FT N

Also found at true corner point, monument marked:

US DEPT OF INTERIOR

T2N R33E

S34 | S35

S3 | S2

T1N

1988

BLM

RECEIVED BY

Umatilla County Surveyors

Date 2-02

Rec'd by KK

No. 02-43-9

LOCATION & COMMENTS:

Corner located at the North edge of bank of small ditch running East-West. Located in old East-West power pole line with farmed fields North & South.

STATE PLANE COORDINATE, OREGON NORTH ZONE, NAD83/91, INT. FOOT:

Indian Allotment Brass Cap witness corner 20 feet North: N = 710928.05

E = 8672176.72

BLM Brass Cap at true corner point:

N = 710908.18

E = 8672177.18

FIRM/AGENCY: William R. Wells
P.O. Box 1696
Pendleton, Oregon 97801

2N33Z17

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 21, 1977
WILLIAM R. WELLS
1106

renews 6-30-02