

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/25/05

CORNER DESIGNATION: 1N33, N-11, The South one-quarter corner of Section 16.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner most recently established by Currin and Noland under Special Contract dated May 4, 1887. Record states: Set basalt stone, 9 x 8 x 7 ins., 6 ins. in the ground for 1/4 sec. cor. marked 1/4 on N. face. Dug pits, 18 x 18 x 12 ins., E. and W. of stone, 5 1/2 ft. dist. and raised mound of earth 1 1/2 ft. high, 3 1/2 ft. base over it.

I find no record of recovery or re-establishment in C.E. Redfield's Notes. Redfield's notes do show a fence line extending South at the corner point but there are no measurements shown.

MONUMENT AND ACCESSORIES FOUND: None. Corner falls in Red Hawk Road.

MONUMENT MARKING DETAIL:

T1N R33E
1 S16
4 S21
2005
PLS 1106

MONUMENT SET:

Re-established corner on line between the recovered Southeast and Southwest corners of Section 16. Held existing fence line, extending South, for departure. At the re-established corner position, set a 2 1/2" brass cap on 2 1/2" by 30" galvanized iron pipe, with cap buried 8" below road surface and marked as shown in Monument Marking Detail.

New accessories:

A 5/8" x 30" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears N 00°42'15" E, 30.00 feet. Set steel post 0.5 feet North of rebar with "witness" sign attached.

A 5/8" x 30" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 54° East, 50.0 feet.

A 5/8" x 30" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears South 24° East, 31.5 feet.

A 5/8" x 24" rebar with a 1 1/4" yellow plastic cap marked "OR PLS 1106, WA PLS 17372", bears North 48° West, 45.2 feet.

All rebar accessories have bearing object signs attached.

LOCATION AND COMMENTS: Corner falls 8 feet South of centerline of Red Hawk Road. A fence line extends South.

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

1N33N11

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-06

RECEIVED BY
Umatilla County Surveyor
Date 6-05
Rec'd By KR
15-1254