

**OREGON CORNER RESTORATION FORM**

**COUNTY:** Umatilla **DATE:** Maintained on 7/26/94. Revisited October 2001, there are no changes from 1994 corner certificate except for new GPS co-ordinate, which is shown on this certificate.

**CORNER DESIGNATION:** Z-1, Southwest corner Section 31, T1N., R34E., W.M.

**PREVIOUS RENEWALS/SURVEYS, ETC.:** Most recent official GLO survey was made by L.E. Wilkes, under Contract No. 29, dated Feb. 20, 1917. Notes state "Set an iron post, 3 ft. long, 2 ins. diam., 24 ins. in the ground, for witness cor. to the standard cor. of Tps. 1 N., Rs. 33 and 34 E., with brass cap (marked as shown in monument detail) and raise a mound of stone, 2 ft. base, 1 1/2 ft. high, N. of cor. This cor. is at the intersection of fences, extending N. and E."

**MONUMENT AND ACCESSORIES FOUND:** Found 2 1/2" brass cap on 2" galvanized iron pipe protruding 14", set by Wilkes in a resurvey for the diminished reservation boundary. Witness corner is 1 link (0.66 feet) West of corner point, listing slightly Southeast, in Southeast corner of rock corner jack. Remnants of old stone mound visible to East of monument.

**MONUMENT MARKING DETAIL:**

G L O  
SC  
T1N  
R33E R34E WC  
S36 | S31  
T1S  
1917

Accessories to existing witness corner monument:

A witness sign is nailed to corner of rock jack.

A 5/8" iron rebar with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 18° E-31.4 feet.

A 5/8" iron rebar with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 57° E-29.2 feet.

A 5/8" iron rebar with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 79° W-27.7 feet.

A 5/8" iron rebar with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 08° W-16.1 feet.

A bearing object sign is attached to each iron rebar accessory. There is a steel fence post near each iron rebar accessory with witness sign attached.

Note: Bearing objects reference the witness corner monument, 1 LK West of true corner point.

**LOCATION & COMMENTS:**

Corner is located at intersection of fences extending West, East and North.

**STATE PLANE CO-ORDINATE:**

Oregon North, NAD 83/91, International Foot:

For true corner point: N = 679511.91 For witness corner monument 1 lk West: N = 679511.89  
E = 8683446.88 E = 8683446.22

**COMPASS DECLINATION:** 18° East.

Surveyor's Seal

**FIRM/AGENCY:** William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

Party Chief: Jason M. Wells, LSIT

Witness: Mark Hammersla

\IN34Z1

RECEIVED BY

Umatilla County Surveyor.

Date 11-01

Rec'd By KK

No. 01-172-2

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

Will. R. Wells

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

renews 6-30-02