

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 10/12/01

CORNER DESIGNATION: Z-25, Township 2 North, Range 33 East, Section 36.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally set by Currin and Noland under Special Contract dated May 4, 1887. Record states: Set a basalt stone, 16x12x8 ins., 11 ins. in the ground for cor. to Tps. 1 and 2 N., R. 33 and 34 East. Marked 6 notches on N., S., E. and W. of cor., 6 ft. dist. Raised earth mound 2 1/2 ft. high, 5 ft. base alongside.

MONUMENT AND ACCESSORIES FOUND:

Found 2 1/2" brass cap on a 2" galvanized iron pipe protruding 8" above ground level, in small mound of stones (marked as shown in monument marking detail). This corner was apparently remonumented by C.E. Redfield, U.S. Indian Service Surveyor, circa 1919, but no notes were found to that effect. Original Currin and Nolin corner stone is at the South side of brass cap monument with an "X" and notches clearly visible.

MONUMENT MARKING DETAIL:

INDIAN ALLOTMENT

T2N

S36 | S31

R33E S1 | S6 R34E

T1N

Set four new accessories:

A brass washer stamped "PLS 1106", 6" above ground level in a 4" diameter hawthorn tree bears N 67° E, 12.7 feet, (true bearing measured with compass).

A railroad spike in approximate centerline of old highway stamped "PLS 1106", bears S 55° 58' E 51.96 feet, (grid bearing and distance).

A railroad spike in approximate centerline of old highway stamped "PLS 1106" bears S 42° 34' W 72.25 feet, (grid bearing and distance).

A brass washer stamped "PLS 1106", 6" above ground level in 6" diameter hawthorn tree bears N 49° W, 30.5 feet, (true bearing measured with compass).

Attached bearing object signs to hawthorn trees. Attached witness sign to hawthorn tree N 15° W, 2.0 feet from corner.

LOCATION AND COMMENTS:

STATE PLANE CO-ORDINATE:

Oregon North, NAD 83/91, International Foot:

N = 711148.78

E = 8682761.20

FIRM: William R. Wells, PLS

P.O. Box 1696

Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

Mark Hammersla

W2N33Z25

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-02

RECEIVED BY

Umatilla County Surveyor

Date 11-01

Rec'd by KK

01-169-R