


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**HISTORY OF ORIGINAL CORNER ESTABLISHED:**

Corner monumented by James Currin and James Noland under special GLO contract dated May 4, 1887. Surveyor General field notes state:

Set basalt stone 12x9x6 in, 8 ins. in the ground marked 1/4 on N. face for 1/4 sec. cor. Raised mound of stone over it.

T 1 N R 34 E N-15



**DESCRIPTION OF CORNER EVIDENCE FOUND:**

None.

SEE SURVEY FOR CTUIR DATED MAY 2019

**DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THIS CORNER:**

At proportionate position, I set a 5/8" x 15" iron pin, drilled 7" into bedrock, with 2 1/2" aluminum cap, marked as shown below, in a collar of stone 2 ft. diam., from which:

**NEW BEARING OBJECTS:**

- A 5/8" x 15" iron pin bears North 33°01' East, a distance of 41.52 feet, with 1 1/2" aluminum cap marked NE RP.
- A 5/8" x 15" iron pin bears South 41°04' East, a distance of 47.23 feet, with 1 1/2" aluminum cap marked SE RP.
- A 5/8" x 15" iron pin bears South 35°32' West, a distance of 32.04 feet, with 1 1/2" aluminum cap marked SW RP.
- A 5/8" x 15" iron pin bears North 41°35' West, a distance of 32.20 feet, with 1 1/2" aluminum cap marked NW RP.

Set a steel fencepost 1 ft. North of corner monument. Fence corner falls Southwest approx. 90 feet.

I hereby certify that the corner was perpetuated on May 14, 2019.  
Witness: Kyle A. Tucker

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR



OREGON  
June 2, 2010  
JEFFREY S. HSU  
83571

Renewal Date: June 30, 2019

GRIFFITH & BLACKMAN

BAGETT

T1N R34E

S15

---

S22

2019

OPLS 83571

1/4

I use a steel tape and magnetic compass in the establishment of the accessories. Magnetic declination used was 13°. Bearings are to a washer in the BT Blaze marked OPLS 83571. Distances are to a 60d spike in the root crown of the tree.