

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


T 1N , R 34E. , W.M.

Corner Code No. T-13

Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by J.P. Currin and J.E. Noland, under Special Contract dated May 4, 1887. The original notes state that at the corner a basalt stone, 12 X 8 X 7, was set 8 ins. in the ground, with a mound of stone raised over it. The stone was marked "1/4" on the west face.



Corner No. Compass Declination: 18.0°

Description of corner evidence found:

Found a 11 X 8 X 5 inch basalt stone, marked "1/4" in a stone mound at an old fence corner. An old fence, now evidenced by rock jack remains, runs north and west.

Description of monument and accessories established to perpetuate the original location of this corner:

At the position of the found original corner stone, set a 2 1/2" brass cap on 1 1/4" by 30 inch galv. iron pipe, 24" in the ground and surrounded with a stone mound. Buried the original corner stone on the north side of the new monument. Set steel fence post South of corner with "Witness Corner" sign attached. No trees or bearing objects are available for references, so I set reference monuments as follows:

- A 1 1/2" alum. cap on a 5/8" by 30" iron pin bears S 56 1/2°E, 26.5 feet.
A 1 1/2" alum. cap on a 5/8" by 30" iron pin bears S 29°E, 45.0 feet.
A 1 1/2" yellow plastic cap on a 5/8" by 30" iron pin bears N 6°E 24.1 feet.
A 1 1/2" yellow plastic cap on a 5/8" by 30" iron pin bears S 67°W 25.9 feet.
The 1 1/2" yellow plastic caps are marked "W.R. Wells, PLS 1106".
The 1 1/2" alum. caps are marked "RM", with an arrow pointing to the corner monument, the distance to the corner monument and "1106".
Set steel fence posts near the reference monuments with the 1 1/2" alum. caps and attached "Bearing Object" sign.
Attached "Bearing Object" signs to the reference monuments with the 1 1/2" yellow plastic caps with wire.

REGISTERED PROFESSIONAL LAND SURVEYOR

William R. Wells

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106

Office of the Surveying Dept. County of Umatilla

State of OR. I hereby certify that the within instrument was filed in this office

for record on the 16th day of January, 1990

David H. Kumbrien by Kathleen K. Ambrose (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY Umatilla County Surveyor Date 1-90 Rec'd by KA No. 90-02-B