


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T 1N, R 34E., W.M.

Corner Code No. T-9  
Note: Monument marked as shown below

History of original corner establishment:

This corner was originally established by Z. F. Moody, under Contract No. 145, dated April 22, 1876. Moody's survey was superseded by a survey by J. P. Currin and J. E. Roland, under Special Contract dated May 4, 1887. The Currin and Roland notes state that at the corner a basalt stone, 14 x 10 x 8 ins. was set 9 ins. in the ground with a mound of stone raised over it. The stone was marked "1/4" on the west face.



Corner No.  
Compass Declination: 18.0°

Description of corner evidence found:

Found a 15" by 10" by 8" basalt stone, marked "1/4" on west face in a small stone mound. There is evidence of an old north-south fence running through the corner point.

Description of monument and accessories established to perpetuate the original location of this corner:

At the position of the found corner stone, set a 2 1/2" brass cap on a 1 1/4" by 30" galv. iron pipe, 16" in the ground to bedrock and surrounded with a mound of earth and stone. Buried the original corner stone in the mound on the north side of the new monument. Set steel fence post North of corner and attached "Witness Corner" sign.

No trees or bearing objects are available for reference, so I set reference monuments as follows:

- A 1 1/2" alum. cap on a 5/8" by 30" iron pin bears S 83 1/2° E, 31.3 feet.
- A 1 1/2" alum. cap on a 5/8" by 30" iron pin bears S 56 1/2° W, 28.3 feet.
- A 1 1/2" yellow plastic cap on a 5/8" by 30" iron pin bears N 52° E, 54.5 feet.
- A 1 1/2" yellow plastic cap on a 5/8" by 30" iron pin bears N 56° W, 37.9 feet.

The 1 1/2" alum. caps are marked "RM", with an arrow pointing to the corner monument, the distance to the corner monument, and "1106". Set steel fence posts near the reference monuments with the 1 1/2" aluminum caps and attached "Bearing Object" signs.

Attached "Bearing Object" signs to the reference monuments with the 1 1/2" yellow plastic caps with wire. The yellow plastic caps are marked "W.R. Wells, PLS 1106".

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of the Survey Dept. County of Umatilla  
State of OR, I hereby certify that the within instrument was filed in this office  
for record on the 16<sup>th</sup> day of January, 1990  
David H. Krambrein by Kathleen K. Amstrong  
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor  
Date: 1-90  
Rec'd by: KA  
No. 90-02-B