

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**


T 1N, R 34E., W.M.

Corner Code No. V-11

Notes: Monument marked as shown below

**History of original corner establishment:**

This corner was originally established by J. P. Currin and J. E. Noland, under Special Contract, dated May 4, 1867. The original notes read, a basalt stone, 4 x 3 x 2 ft. in place, which I marked for 1/4 Sec. Cor. with 1/4 on N face, and a cross ill at exact corner point and a mound of stone alongside, pits impracticable.



Corner No.  
Compass Declination: 18.0°

**Description of corner evidence found:**

A 4' by 3' by 2' out of the ground basalt stone in place, marked "X" on top. The "1/4" marks called for on the north side of the rock were not found and are believed to have broken off and rolled down the steep hillside.

The remains of an old east by west fenceline are visible west of the corner point.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

Set a 3" dia. brass rock disk at the location of the "X" with mortar.

No trees are available for reference so I mark bearing objects as follows:

- A 2' by 1 1/2' by 1 1/2' out of the ground basalt rock outcrop bears S 67 1/2°E, 18.4 feet, marked "X BO" on top.
- A 6' by 5' by 2' out of the ground rock outcrop bears S 16°E, 13.2 feet, marked "X BO" on top.
- A 3 1/2' by 2 1/2' by 3' out of the ground rock outcrop bears S 37°W, 16.6 feet, marked "X BO" on west face.
- A 3 1/2' by 3 1/2' by 3' out of the ground rock outcrop bears N 27°W, 8.1 feet, marked "X BO" on top.

Measurements to the bearing objects are taken to the "X" on the "X BO" markings.

Set steel fence post 10 feet west of corner and attached "Witness Corner" sign.

REGISTERED PROFESSIONAL LAND SURVEYOR  <i>William R. Wells</i> OREGON JULY 22, 1977 WILLIAM R. WELLS 1106
---

Office of the Survey Dept. County of Umatilla  
 State of OR I hereby certify that the within instrument was filed in this office  
 for record on the 16<sup>th</sup> day of January, 1990  
 David A. Krumbein by Kathleen L. Amshery  
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY  
 Umatilla County Surveyor  
 Date 1-90  
 Rec'd by KA  
 No. 90-02-B