

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 9/19/94

CORNER DESIGNATION: Z-11. South 1/4 corner Section 33, T1N., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Set basalt stone, 24x12x6 ins., 18 ins. in the ground, for 1/4 sec. cor. marked S C 1/4 on N. face, and raised mound of stone 1 1/2 ft. high, 3 1/2 ft. base over it."

MONUMENT AND ACCESSORIES FOUND: After confirmation by survey, accepted ancient fence corner as best remaining evidence of the original corner position.

**MONUMENT MARKING DETAIL:**

T1N R34E  
1/4 S33  
-----  
SC  
1994  
PLS 1106

MONUMENT SET: At position of fence corner, set a 1 1/2" aluminum cap on a 5/8" x 5" iron pin, set in drilled hole in solid basalt, (marked as shown in the monument detail). Attached witness post sign to corner jack post 0.3 feet North of monument.

**New Accessories:**

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 26° W-39.6 feet.  
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 14° W-33.8 feet.  
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 39° E-25.3 feet.  
"XBO" chiseled on 3' x 2.5' x 1.2' rock outcrop, bears N 58° E-13.5 feet.  
Attached bearing object signs to each iron pin, set steel fence post near each iron pin with witness sign attached.  
Measured to "X" on the "XBO" marks.

**LOCATION & COMMENTS:**

Corner located at fence intersection with fences running North and West.

**STATE PLANE CO-ORDINATE:**

Oregon North Zone, NAD 83/91, U.S. Survey Foot:  
N = 679815.61  
E = 8696798.64

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

Party Chief: Robert D. English  
Notes: Robert D. English  
Witness: F. Scot Munro

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

RECEIVED BY  
Umatilla County Surveyor  
Date 2-95  
Rec'd By SK  
No. 95-16-C

Renews 6/30/96