

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla      DATE: 9/19/94

CORNER DESIGNATION:    Z-13.    Southeast corner Section 33, T1N., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Set basalt stone, 18 x 14 x 8 ins., 12 ins. in the ground, for cor. to secs. 33 and 34 marked S C with 3 notches on E. and W. edges, and raised mound of stone 2 ft. high, 4 1/2 ft. base over it."

MONUMENT AND ACCESSORIES FOUND: Found mound of stone with 18" x 12" x 6" stone, with visible marks "SC" and notches visible.

**MONUMENT MARKING DETAIL:**

T1N    R34E  
33 | 34  
-----  
      SC  
T1S    R34E  
1994  
PLS 1106

MONUMENT SET: At position of found corner stone, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, 12" in the ground with mound of stone to cap, (marked as shown in the monument detail).

**New Accessories:**

Attached witness sign to existing steel fence post 1.3 feet West of monument.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 72° W-32.6 feet.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 18° W-36.3 feet.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 55° E-43.1 feet.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 71° E-37.7 feet.

Attached bearing object signs to each iron pin. Set a steel fence post near each iron pin with witness sign attached.

**LOCATION & COMMENTS:**

**STATE PLANE CO-ORDINATE:**

Oregon North Zone, NAD 83/91, U.S. Survey Foot:  
N = 679900.60  
E = 8699437.78

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

Party Chief: Robert D. English  
Notes: Robert D. English  
Witness: F. Scot Munro

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6/30/96*

RECEIVED BY

Umatilla County Surveyor

Date 2-95

Rec'd By KK

No. 95-16-C