

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 9/20/94

CORNER DESIGNATION: Z-21. Southeast corner Section 35, T1N., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Set basalt stone 18x18x5 ins. 12 ins. in the ground, for cor. to secs. 35 and 36, marked S C with 1 notch on E. and 5 notches on W. edges, and raised mound of earth and stone, 2 1/2 ft. high, 5 1/2 ft. base over it."

MONUMENT AND ACCESSORIES FOUND: Found mound of stone within 34' of record distance. Stone close to 18x18x5 dimensions. No discernable marks. Accepted stone mound as best available evidence of corner location.

MONUMENT MARKING DETAIL:

T1N R34E
S35 ; S36

SC
T1S R34E
1994
PLS 1106

MONUMENT SET: At center of found stone mound, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, 16" in the ground, with mound of stone to cap (marked as shown in the monument detail).

New Accessories:

Set steel fence post 3.0 feet North of monument, with witness sign attached.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 80° W-9.8 feet.

A 20" douglas fir bears N 01° W-44.0 feet, scribed: T1N R34E S35 SC BT.

A 15" douglas fir bears N 24° E-63.5 feet, scribed: T1N R34E S36 SC BT.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 60° E-22.3 feet.

Attached bearing object signs to each iron pin. Set a steel fence post near each iron pin with witness sign attached. Bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached bearing object and witness signs to each tree; painted a 6" band and face of blaze red.

LOCATION & COMMENTS:

STATE PLANE CO-ORDINATE:

Oregon North Zone, NAD 83/91, U.S. Survey Foot:

N = 680162.28

E = 8710140.32

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Robert D. English

Notes: Robert D. English

Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/96

RECEIVED BY
Umatilla County Surveyor
Date KK
Rec'd By 2-95
No. 95-16-C