

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 9/17/94

CORNER DESIGNATION: Z-23. South 1/4 corner Section 36, T1N., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Set basalt stone, 18x9x6 ins., in mound of stone, 2 1/2 ft. base, 5 1/2 ft. high, on S.W. side of hill. Pits impracticable, marked stone S C 1/4 on N. face."

MONUMENT AND ACCESSORIES FOUND: None. Corner re-established using single proportionate measurement taken from the recovered Southwest corner Section 36 and the recovered Southeast corner Section 36, using James P. Currin and James Noland record under GLO Contract dated May 4, 1887.

MONUMENT MARKING DETAIL:

T1N R34E
 1/4 S36

 SC
 1994
 PLS 1106

MONUMENT SET: At position determined by survey, set a 1 1/2" aluminum cap on a 5/8" x 5" iron pin, driven into hole drilled in solid basalt, (marked as shown in the monument detail).

New Accessories:

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 71° W-31.1 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 08° W-16.9 feet.
"XBO" chiseled on smooth vertical face of basalt ravine bottom, bears N 46° E-16.1 feet. Measured to "X" on the "XBO" marks.
"XBO" chiseled on smooth vertical face of basalt ravine bottom, bears N 78° E-12.8 feet. Measured to "X" on the "XBO" marks.

Attached bearing object signs to each iron pin, and nailed signs to rock near "XBO" with concrete nails. Set a steel fence post near each pin with witness sign attached.

LOCATION & COMMENTS: Corner falls on extremely steep south slope.

STATE PLANE CO-ORDINATE:

Oregon North Zone, NAD 83/91, U.S. Survey Foot:
N = 680231.06
E = 8712761.88

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/96

RECEIVED BY
Umatilla County Surveyor
Date 2-95
Rec'd By KK
No. 95-16-C