

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** Remonumented 7/11/94. Revisited October 2001, there are no changes from 1994 corner certificate except for new GPS co-ordinate, which is shown on this certificate.

CORNER DESIGNATION: Z-25. Southeast corner Section 36, T1N., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Found old corner, which is a post, 4 ft. long, 4 ins. square, still standing but badly decayed. Marked T.1N, R.34E., Sec. 36 on N.W., T.1N, R.35E., Sec. 31 on N.E. faces with mound of stone alongside. I reestablish this cor. by setting post, 4 ft. long, 4 ins. square, 24 ins. in the ground, for cor. to T.1N., Rgs. 34 and 35 E. marked S C T 1 N on N., R 35 E S 31 on E., and R 34 E S 36 on W. faces with 6 notches on N. E. and W. edges, and raised mound of stone 2 1/2 ft. high, 5 1/2 ft. base over it."

Record 95-16-C, 7/11/94: Found mound of stone, mound is reasonably intact on east edge of small drainage at brow of hill into Bell Cow Canyon. Nothing found of post. Jim Hambleton had placed a nail in the mound during an earlier timber survey.

MONUMENT MARKING DETAIL:

TIN
R34E R35E
S36 | S31

S1
T1S
1994
PLS 1106

MONUMENT AND ACCESSORIES FOUND: Found a 2 1/2" brass cap on a 1 1/4" galvanized iron pipe, set 28" in the ground, (marked as shown in the monument detail).

Accessories:

A steel fence post 2.5 feet North of monument with witness sign attached.

A 5/8" iron rebar with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 76° E-24.9 feet.

A 5/8" iron rebar with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 78° E-64.2 feet.

A 5/8" iron rebar with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 29° W-45.0 feet.

A 5/8" iron rebar with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372" bears N 09° W-48.5 feet.

Bearing object signs are attached to each iron rebar. There is a steel fence post near each iron rebar with witness sign attached.

LOCATION & COMMENTS:

STATE PLANE CO-ORDINATE:

Oregon North Zone, NAD 83/91, International Foot:

N = 680301.19

E = 8715400.97

COMPASS DECLINATION: 18° East.

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Jason M. Wells, LSIT
Witness: Mark Hammersla
\\N34Z25

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

re news 6-30-02

RECEIVED BY

Umatilla County Surveyor

Date 11-01

Rec'd By KK

No. 01-172-2