

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 10/5/94

CORNER DESIGNATION: Z-3. South 1/4 corner Section 31, T1N., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state "Set basalt stone, 20x10x10 ins., 14 ins. in the ground, for 1/4 sec. cor. marked S C 1/4 on N. face and raised mound of stone 1 1/2 ft. high, 3 1/2 ft. base over it." Corner found by L.E. Wilkes, under Instructions dated Feb. 20, 1917. Notes state: "From the standard 1/4 sec. cor. on the S. bdy. of sec. 31, T.1 N., R. 34 E., which is a basalt stone, 8x6x6 ins. above ground, firmly set, marked and witnessed as described by the surveyor general, S.89°54'W., retracing the S. bdy. of sec. 31; at 7.17 chs. fall 2 lks. N. of the closing cor. of Tps. 1 S., Rs. 33 and 34 E. and at 43.24 chs. fall 12 lks. S. of the standard cor. of Tps. 1 N., Rs. 33 and 34 E."

MONUMENT AND ACCESSORIES FOUND: None. Corner position was re-established using L.E. Wilkes tie from the Northwest corner of Section 6, T 1 S., R 34 E.. Wilkes reported tie of 7.17 chains was adjusted proportionally to fit the measured distance between the Southwest corner of Section 31, T 1 N., R 34 E., and said Northwest corner of Section 6.

MONUMENT MARKING DETAIL:

T1N R34E
1/4 S31

 SC
T1S R34E
1994
PLS 1106

MONUMENT SET: At position determined by survey, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, 26" in the ground with mound of stone to cap, (marked as shown in the monument detail).

New Accessories:

Set steel fence post 1.8 feet North of monument with witness sign attached.

A 7" ponderosa pine bears N 35°E-97.4 feet, scribed: 1/4 S31 SC BT.

A 19" ponderosa pine bears N 46° E-125.0 feet, scribed: 1/4 S31 SC BT.

A 26" ponderosa pine bears N 59° E-87.2 feet, scribed: 1/4 S31 SC BT.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106" bears N 32° W- 9.3 feet.

Attached bearing object signs to iron pin. Set a steel fence post near iron pin with witness sign attached. Bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached bearing object and witness signs to each tree, painted a 6" red band and face of blaze red.

LOCATION & COMMENTS:

Corner falls North of East-West fence.

STATE PLANE CO-ORDINATE:

Oregon North Zone, NAD 83/91, U.S. Survey Foot:

N = 679576.05

E = 8686276.56

RECEIVED BY
Umatilla County Surveyor
Date 2-95
Rec'd By KK
No. 95-16-C

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801
Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/96

RECEIVED BY

Umatilla County Surveyor

Date 2-95

Rec'd By RR

No. 95-16-C