

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla      DATE: 10/4/94

CORNER DESIGNATION:    Z-7.    South 1/4 corner Section 32, T1N., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "A cottonwood tree, 12 ins. diam., which I mark S C 1/4 S on N. face for 1/4 sec. cor., and raised mound of earth and stone alongside."

MONUMENT AND ACCESSORIES FOUND: None. Corner re-established by single proportionate measurement between the re-established South 1/4 corner of Section 31 and the recovered South 1/4 corner Section 33, using James P. Currin and James Noland records under GLO Contract dated May 4, 1887.

**MONUMENT MARKING DETAIL:**

T1N            R34E  
              1/4 S32  
              -----  
              SC  
T1S            R34E  
              1994  
              PLS 1106

MONUMENT SET: At position determined by survey, set a 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, 30" in the ground, (marked as shown in the monument detail).

**New Accessories:**

Set a steel fence post with witness sign attached 2.0 feet North of monument.

A 16" ponderosa pine bears N 80° W-76.5 feet, scribed: 1/4 S32 SC BT.

A 20" ponderosa pine bears N 70° W-51.2 feet, scribed: 1/4 S32 SC BT.

An 11" ponderosa pine bears N 07° E-39.9 feet, scribed: 1/4 S32 SC BT.

A 6" ponderosa pine bears N 32° E-54.7 feet, scribed: 1/4 S32 SC BT.

Bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached bearing object and witness signs to each tree; painted a 6" band and face of blaze red.

LOCATION & COMMENTS: Corner falls on west bank of Calamity Creek.

**STATE PLANE CO-ORDINATE:**

Oregon North Zone, NAD 83/9/, U.S. Survey Foot:  
N = 679695.83  
E = 8691537.60

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

Party Chief: Robert D. English  
Notes: Robert D. English  
Witness: F. Scot Munro

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Renews 6/30/96

RECEIVED BY  
Umatilla County Surveyor  
Date 2-95  
Rec'd By AK  
No. 95-16-C