

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 10/19/01

CORNER DESIGNATION: Z-25, Township 2 North, Range 35 East, Section 36.

PREVIOUS RENEWALS/SURVEYS ETC.: Corner was originally established by Z. F. Moody, U.S. Deputy Surveyor, under Contract No. 145, dated April 23, 1871, notes state: Set post for corner to Townships 1 & 2 North, Ranges 35 & 36 East, Willamette Meridian, from which: A fir 20 ins. in diam. bears S 80° W., 30 lks. A fir 18ins. in diam. bears N 10° W., 20 lks.. In 1882, Herman D. Gradon, under Contract No. 452 ties into the corner and reports finding a post, from which: A fir 14 ins. diam. bears N 5° W., 21lks. And a fir, 20 ins. diam. bears S 52° W 31lks. In 1895, Marius Buchanan, under Contract No. 635 ties into the corner and calls a post marked and witnessed as described by Surveyor General. In July, 1919, C.E. Redfield, U.S. Indian Service Surveyor, claims to have recovered only the NW original fir BT which he opened to reveal scribes. Redfield's given dimensions of N 15° W 27 lks to the NW for BT do not match any record.

In U.S. Department of the Interior, Dependent Resurvey of a Portion of the West Boundary, T.1N., R36E., W.M., Oregon, dated 1998. Notes state: Set a stainless steel post, 28 ins. long, 2 1/2 ins. diam., 22 ins. in the ground, with brass cap (marked as shown in monument marking detail), from which: A Douglas fir, 12 ins. diam., bears N 48° E, 18 lks. Dist., mkd. T2N R36E S31 BT. A Douglas fir, 10 ins. diam., bears S 56° E, 20 1/2 lks. Dist., mkd. T1N R36E S6 BT. A Douglas fir, 15 ins. diam., bears S 26° W, 29 lks. Dist., mkd. T1N R35E S1 BT. A Douglas fir, 15 ins. diam., bears N 87 1/2° W, 7 lks. dist., mkd. T2N R35E S36 BT. Deposit a magnet in a white plastic case at the base of the stainless steel post. This corner was reestablished by survey. BLM Survey is recorded as Survey No. 00-110-B.

MONUMENT AND ACCESSORIES FOUND: Found a 3" brass cap on 2 1/2" stainless steel pipe, 4" above ground level, marked as shown in "monument marking detail".

Accessories found, (From unrecorded 1998 BLM Survey):

- A 12" fir with blaze pitched over bears N 48° E, 11.9 feet.
  - A 10" fir with blaze pitched over bears S 56° E, 13.5 feet.
  - A 14" fir with pitched over blaze bears S 26° W, 19.1 feet.
  - A 14" fir with blaze pitched over bears N 87 1/2° W, 4.6 feet.
- All bearing trees have bearing tree signs attached, from 1998 BLM Survey.

**MONUMENT MARKING DETAIL:**  
US DEPT OF THE INTERIOR

T2N  
R35E | R36E  
S36 | S31  
S1 | S6  
T1N  
1998  
BLM

LOCATION AND COMMENTS:  
Redfield's location for this corner would place it West and North of the existing BLM monument.

STATE PLANE CO-ORDINATE:  
Oregon North, NAD 83/91, International Foot:  
N= 712839.39  
E=8746218.50

FIRM: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East Surveyor's Seal

Witnesses: Jason Wells, LSIT  
Mark Hammersla  
V2N35Z25

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-02*

RECEIVED BY  
Umatilla County Surveyor  
Date 11-01  
Rec'd By KF  
Sta. 01-121-R