

OREGON CORNER RESTORATION FORM

Section 20 Township 1N Range 35E
 County Umatilla Date: September 29, 2008

Corner Designation: 1N35N5

Corner to sections 17, 18, 19, and 20, T1N, R35E,
 W.M., Umatilla County, Oregon.

Condition Report Only
 Not found
 Remonumented
 Unrecorded
 Surveyed in
 Referenced out


Previous Renewals / Surveys, etc.

This corner was originally set by James Currin and James Noland under special instructions dated May 4, 1889. Their record reads: Set post 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to secs. 17, 18, 19 & 20, marked T1N, S17 on N.E.; R35E. S20 on S.E.; S19 on S.W. and S18 on N.W. faces, with 3 notches on S. and 5 notches on E. edges from which a fir, 18 ins. in diam. bears N25°E 18 lks. dist., marked T1N S17 BT; a Fir 6 ins. in diam. bears S30°E 25 lks. dist, marked R35E S20 BT; a Fir 10 ins. in diam. bears S10°W 38 lks. dist., marked T1N S19 BT; a Fir 12 ins. in diam. bears N20°W. 10 lks. dist. marked R35E S18 BT.

Monument and Accessories found: (condition and source)
 None. The point falls in the center of a dirt logging road.

DIAGRAM

SKETCH



MONUMENT (S) AND ACCESSORIES SET (Procedures and Description)

At the proportionate position I set a 1 1/2" x 30" galvanized iron pipe with a 2 1/4" brass cap stamped as shown in the diagram above 32 inches in the ground.

For references, I set four, 5/8" by 24" rebars with 1 1/8" orange plastic caps attached, stamped WTS and 56295LS as described below:

- an iron rebar bears N67°51'08"E, 35.22 feet ;
- an iron rebar bears N57°05'21"W, 37.57 feet;
- an iron rebar bears S41°16'08"W, 34.40 feet;
- an iron rebar bears S28°58'11"E, 52.92 feet;

The monument was set and references were tied using a Trimble 5601 Robotic total station.

Location and comments

Compass Declination

Surveyors Seal

RECEIVED BY:
Umatilla County Surveyor
 Date: 10/27/08
 Rec'd By: [Signature]
 No. 08-145-B

Firm / Agency
 Witness Tree Surveying
 Address
 P.O. Box G
 Pilot Rock, Or. 97868
 Party Chief
 Stephen K, Haddock

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Stephen K. Haddock

OREGON
 JULY 9, 2001
 STEPHEN K. HADDOCK
 56295LS

RENEWAL DATE 6-30-09