

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 11/03/21

CORNER DESIGNATION: P-9, The East one-quarter corner of Section 20, Township 1 North, Range 35 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC: Corner was originally established by Deputy Surveyor's Currin and Noland, under Special Contract Dated May 4, 1887. Notes state:

"Top of Ridge, N.E. & S.W., and Set Stone, 12 X 12 X 10 ins. 8 ins. In the ground for 1/4 Sec. cor., marked "1/4" on West face and raised mound of stone over it. Pits Impactable".

In Survey No. 320, dated June 8, 1910, County Surveyor John Kimbrell, recovered the corner but does not state what was recovered.

Around 1941, Bonneville Power Administration surveyors recovered a "mound of stone" 2662.6 feet South of the Northeast corner of Section 20. BPA map does not note the existing down fence and two stone mounds about 18 feet West of the computed corner point. BPA coordinates indicate their "mound" was on line between the Southeast and Northeast corners of Section 20. No mound exists at the BPA location at this time. BPA map does note an East-West fence near the location of the North 1/16th corner between Secs. 20 and 21. Rebuilt portions of that fence still exist.

In Record Survey No. 88-11-B, John E. Hollingsworth declared the corner lost and computed it's position at the mid-point between the Southeast and Northeast corners of Section 20. The Hollingsworth survey subdivided Section 20 for the Oregon State Parks & Recreation Division.

MONUMENT AND ACCESSORIES FOUND: None. I made a thorough search for the corner stone without success. There is a down fence line through the corner area, about 18 feet West of the set corner monument, and 2 stone mounds on the rocky ridge top. The mounds appear to have been made as fence braces to the down fence. I reestablish this corner by single proportion measurement, in conformance with Record Survey No. 88-11-B.

MONUMENT MARKING DETAIL:

T1N R35E  
1/4  
S20 | S21  
2021  
PLS 1106

MONUMENT SET: At the reestablished corner point, set a 2 inch aluminum cap on 5/8 by 24 inch pointed rebar in a drilled hole on the rocky ridge top, and surrounded with stones. Cap marked as shown in Monument Marking Detail. Placed a "Witness" sign in the stone mound. There is an old survey lath, lying in the corner area, most likely from the corner search on Survey No. 88-11-B.

New accessories:

A 12 inch ponderosa pine bears N 28° E, 58.9 feet, scribed 1/4 S21 BT on single blaze.

A 12 inch ponderosa pine bears N 64° E, 45.0 feet, scribed 1/4 S21 BT on single blaze.

A 12 inch ponderosa pine bears S 73° E, 79.5 feet, scribed 1/4 S21 BT on single blaze.

A 8 inch ponderosa pine bears N 21° W, 80.1 feet, scribed 1/4 S20 BT on single blaze.

Nailed "Bearing Object" sign to each new bearing tree.

LOCATION AND COMMENTS: Corner is located on a bare rocky bare ridge top about 160 feet East of the BPA Pendleton-LaGrande power Transmission line.

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-22*

\1N35P-9

*21-121-B*