


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**HISTORY OF ORIGINAL CORNER ESTABLISHMENT:**

In 1975, corner established by Chris Palmer in survey filed as 03-274-C. No monumentation record could be found.

T 1 N R 35 E R-02



**DESCRIPTION OF CORNER EVIDENCE FOUND:**

Found 1 1/2" iron pipe with 2" brass cap, marked as shown below, 13 inches above ground, from which:

A 14 inch Ponderosa Pine bears North 60° East, a distance of 13.85 feet, alive and vigorous with scribe marks visible on a partially healed blaze.

**DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED**

**TO PERPETUATE THE ORIGINAL LOCATION OF THIS CORNER:**

From the iron pipe monument, I take a new bearing tree.

A double boled Ponderosa Pine tree, the left bole of which is 11 inches diam., bears South 46° East, a distance of 24.40 feet, marked W 1/6 S30 BT.

I hereby certify that the corner was perpetuated on August 19, 2013.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR



OREGON  
June 2, 2010  
JEFFREY S. HSU  
83571

Renewal Date: June 30, 2015

T1N R35E

W 1/16     S 19  
                  —  
                  S 30

1975

PE 8508

I used a steel tape and magnetic compass in the recovery of the bearing tree and establishment of new tree. I used 16° East magnetic declination and the bearings and distances are to the center of root crown on old bearing tree. Distance is to a 60d spike in the right hand side of the new tree. Bearing is to a brass washer marked OPLS 83571 in the lower BT blaze.

**RECEIVED BY**  
Umatilla County Surveyor  
Date: 9/20/2013  
Rec'd By: Dany Fehak  
No: 13-521-B