

42" Tamarack N35°E, 13 links "T1N S21 BT" (not found).

10" black pine S75°E, 61 links "R35E S28 BT" (not found).

20" fir S20°W, 21 links "T1N S29 BT". (Parks Crew found 2' rotten stump S20°W, 14.7' to center.)

12" Tamarack N70°W, 29 links "R35E S20 BT". (Parks Crew found 18" Tamarack snag N74°W, 19.6' to center, trace of scribe visible, has a Georgia Pacific corner tag.

Witnessed by:

R. Hemmer
L. Boge

North 1/16 Corner Sections 29 and 28

S-9

Parks Crew Set:

Var. 20½°

5/8"x30" capped iron rod with aluminum cap marked "Oregon State Parks" and erected mound of stone around iron rod.

9" pine N80°E, 37.4' to center, scribed "N1/16 S28 BT RS691".

8" pine N88°W, 35.1' to center, scribed "N1/16 S29 BT". Set Parks corner tag.

Old rock pile at fence corner south 7.0'.

Witnessed by:

R. Hemmer
L. Boge
L. Hettema

¼ Corner Sections 29 and 28

T-9

Original:

Var. 20°

Set basalt stone 12"x10"x7", 8" in ground for ¼ section corner, marked ¼ on west face (not found) from which:

A 12" red fir N62°E, 12 links "¼S BT" (not found).

A 24" black pine S60°W, 42 links "¼S BT" (not found).

Parks Crew Reestablishment:

Set:

5/8"x30" capped iron rod marked "Oregon State Parks" and erected a 2.0' high by 3.0' diameter concreted mound of rocks. Scratched in concrete around cap "¼, 29, 28".

Highway sight post bears N11°E, 13.6'.

Highway sign post bears S41°E, 119.8'.

Placed Parks corner tag on south side of mound and covered with loose rocks.

Corner lands at bottom of Highway cut bank.

Witnessed by:

R. Hemmer
L. Boge

RECEIVED BY

Umatilla County Surveyor

Date _____

Rec'd by _____

No. S-124