

Section Corner 29|28
32|33

V-9

Original:

Var. 20°

Set basalt stone 12"x10"x8", 8" in ground, 1 notch on south and 4 notches on east edges.

10" pine N44°E, 18 links "T1N S28 BT".

12" pine S67°E, 22 links "R35E S33 BT".

10" pine S55°W, 11 links "T1N S32 BT".

12" pine N75°W, 14 links "R35E S29 BT".

Parks Crew Found:

3/4" iron pipe 1.0 above ground.

17" fir N88°E, 13.0' to center, marked "S28, T1N, R35E, BT".

16" fir S20°E, 34.3' to center, marked "S33, T1N, R35E, BT"

These bearing trees were scribed by Donald Staebler in 1969.

15" pine N10°W, 18.7' to center had chopping marks on it, but no scribe visible.

8" pine S64°W, 12.5' to center, has Forest Service corner tag.

Witnessed by:

R. Hemmer
L. Boge

1/2 Corner Sections 29 and 32

V-7

Original:

Set post 3' long, 3" square, 24" in ground, marked "1/2 S" on north face (not found).

16" fir N51°W, 125 links "1/2 S BT" (not found).

25" pine S65°W, 76 links ("1/2 S BT" (not found).

Parks Crew Reestablishment:

Set:

5/8"x30" capped iron rod marked "Oregon State Parks".

7' fiberglass post 2.0' south of iron rod.

10" Tamarack S8°E, 31.1' to center, scribed "N 1/2 S32 BT". Set Parks corner tag.

12" fir N53°W, 33.8' to center, scribed "S 1/2 S29 BT RS691".

Witnessed by:

A. Slack
R. Hemmer
L. Boge
S. Morrison

RECEIVED BY
Umatilla County Surveyor
Date _____
Rec'd _____
No. 3-124