

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla      DATE: 8/06/97

CORNER DESIGNATION: X-15, Center 1/4 corner Section 34, T1N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: No record was found. Corner established as part of this survey.

MONUMENT AND ACCESSORIES FOUND: Corner established as part of this survey.

**MONUMENT MARKING DETAIL:**

OR PLS 1106  
WA PLS 17372

**MONUMENT SET:**

At position determined by survey, set a 5/8" by 30" iron pin, capped with a 1 1/2" yellow plastic cap, marked as shown in corner diagram, 28" in the ground from which:

**New Accessories:**

A 6" lodgepole pine bears S 06° W 10.2' scribed C1/4 S34 BT.  
A 5" lodgepole pine bears S 58° E 15.4' scribed C1/4 S34 BT.  
A 5" lodgepole pine bears S 85° E 8.9' scribed C1/4 S34 BT.  
A 6" lodgepole pine bears N 08° W 41.1' scribed C1/4 S34 BT.

Attached witness sign to steel fence post 1' Northwest of corner.  
Attached bearing object signs to the bearing trees.

LOCATION & COMMENTS:      Corner located 50 East of gravel road running North.

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

Witness: John Linder & Jason Wells.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*renews 6-30-98*

*97-156-B*