

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 7/28/94

CORNER DESIGNATION: Z-13. Southeast corner Section 33, T1N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Set post 4 ft. long, 4 ins. square, 24 ins. in the ground in exact place of old cor. for cor. to secs. 33 and 34 marked S.C. T.1N. R.35E. on N., S34 on E. and S.33 on W. faces, with 3 notches on E. and W. edges, from which: A Fir, 10 ins. in diam. bears N 40° E 46 lks., marked S.C.T1N.R.35 E.S34 B.T.

A Hemlock, 18 ins. in diam. bears S 40° E 19 lks. dist., marked S.C.T.1 S.R.35 E. B.T. A Hemlock, 8 ins. in diam. bears N85°W.68 lks dist., marked S.C.T1N.R.35 E. S.33 B.T. The old bearing trees at this cor. are all dead and some of them are fallen."

References to old corner and accessories are from original survey record by Timothy Davenport, Contract No. 102, dated July 20, 1863. Corner remonumented by Umatilla County Surveyor in 1967.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on a 1" galvanized iron pipe, protruding 5" out of the ground, (marked as shown in monument detail).

Bearing Trees:

A 14" spruce bears S 43° E-11.9 feet, with healed blaze, (1967 bearing tree).

MONUMENT MARKING DETAIL:

UMATILLA COUNTY

SURVEYOR

T.1N. R.35E.

33 | 34

4 | 3

T.1S. R.35E.

1967

MONUMENT SET:

New Accessories:

Attached witness sign to existing steel fence post 1.7 feet Northeast of monument.

A 9" spruce bears N 36° E-23.7 feet, scribed: T1N R35E S34 SC BT.

A 7" spruce bears S 62° W-10.6 feet, scribed: T1S R35E S4 SC BT.

A 6 1/2" spruce bears N 75° W-11.1 feet, scribed: T1N R35E S33 SC BT.

New bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached bearing object and witness signs to all bearing trees, painted a 6" band and face of blaze red.

LOCATION & COMMENTS:

STATE PLANE CO-ORDINATE:

Oregon North Zone, NAD 83/91, U.S. Survey Foot:

N = 680660.94

E = 8731246.14

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/96

RECEIVED BY
Umatilla County Surveyor
Date 2-95
Rec'd By KK
No. 95-16 P