

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 9/7/94

CORNER DESIGNATION: Z-17. Southeast corner Section 34, T1N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by Manius Buchanan, under Contract No. 635, dated April 19th, 1895. Notes state: "Found a tamarac post 5 ins. square set firmly in the ground, from which: A pine 25 ins. in diam. bears N. 35° E. 86 lks. dist., marked T.1 N.R. 35 E. S.35 B.T., and An alder 5 ins. in diam. bears S.39° E. 20 1/2 lks. dist., marked T.1 S.R. 35 E. S. 2 B.T."

Buchanan found remains of original corner which was originally established by Timothy Davenport under Contract No. 102, dated July 20, 1863 and perpetuated by Currin and Noland as reported in Special Contract dated May 4, 1887.

MONUMENT AND ACCESSORIES FOUND: Found 31" ponderosa pine bearing tree, healthy with visible scribing. Marked by Buchanan in 1895, bears N 35° E-86 lk (56.8 feet).

**MONUMENT MARKING DETAIL:**

T1N R35E  
S34 | S35  
-----  
S3 | S2  
T1S R35E  
1994  
PLS 1106

**MONUMENT SET:**

At a point S 35° W-56.8 feet (86 LK) from the center of found bearing tree, set 2 1/2" brass cap on 1 1/4" x 30" galvanized iron pipe, 30" in the ground, built rock mound to cap, (marked as shown in monument detail).

Set steel fence post 2.5 feet North of monument with witness sign attached.

**New Accessories:**

A 15" lodge pole pine bears N 05 1/2° W-33.3 feet, scribed: T1N R35E S34 SC BT.

A 12" ponderosa pine bears S 42° E-69.9 feet, scribed: T1S R35E S2 SC BT.

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1106-WA PLS 17372", bears S 11 1/2° W-62.2 feet.

Bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached bearing object and witness signs to each tree, painted a 6" band and face of blaze red. Attached bearing object sign to iron pin. Set steel fence post near pin with witness sign attached.

LOCATION & COMMENTS: Corner is on east bank of Meacham Creek 200 feet more or less, South of UPRR tracks.

**STATE PLANE CO-ORDINATE:**

Oregon North Zone, NAD 83/91, U.S. Survey Foot:

N = 680791.47  
E = 8736535.25

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801  
Party Chief: Robert D. English  
Notes: Robert D. English  
Witness: F. Scot Munro

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Will. R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*RENEWS 6/30/96*

RECEIVED BY  
Umatilla County Surveyor  
Date 2-95  
Rec'd By RK  
No. 95-16-C