

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 7/28/94

CORNER DESIGNATION: Z-9. Southeast corner Section 32, T1N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Set post 4 ft. long, 4 ins. square, 24 ins. in the ground in exact place of old post which is badly decayed, for cor. to secs. 32 and 33, marked S.C.T.1 N.R.35E. on N., S33 on E. and S.32 on W. faces with 4 notches on E. and 2 notches on W. edges, from which: A Hemlock 18 ins. in diam. (old bearing tree) bears S.40°E. 19 lks. dist., markd S.C.T.1 S.R.35 E. B.T. A Red Fir, 14 ins. in diam. (old bearing tree) bears N20°W.52 lks. dist., marked S.C.T.1N.R.35 E. S.32 B.T. A Red Fir, 10 ins. in diam. (old B.T.) bears N.40 E. 46 lks. dist. marked S.C.T.1 N.R.35 E.S.33 B.T. Reference to original post and bearing trees from survey made by Timothy Davenport, under Contract No. 102, dated July 20, 1863. Corner was remonumented by PLS 1106 in 1983. Record No. 85-13-R.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on a 2 1/2" galvanized iron pipe, protruding 2" out of the ground, (marked as shown in monument detail).

Bearing Trees:

A 19" white fir stump bears N 25° E-31.2 feet, with visible scribing.

A 10" western larch bears S 57° W-33.4 feet, with open blaze and visible scribing.

An 11" white fir bears N 62° W-25.0 feet, with open blaze and visible scribing.

MONUMENT MARKING DETAIL:

1983
T1N R35E
32 | 33

5 | 4
T1S R35E
PLS 1106

MONUMENT SET:

New Accessories:

Set steel fence post 1.9 feet East of monument with witness sign attached.

A 9" tamarack bears N 55 1/2° E-81.8 feet, scribed: T1N R35E S33 SC BT.

A 15" ponderosa pine bears S 25° E-85.2 feet, scribed: T1S R35E S4 SC BT.

Bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached bearing object and witness signs to each tree, painted a 6" band and face of blaze red.

LOCATION & COMMENTS:

Corner is located just West of North-South fence.

STATE PLANE CO-ORDINATE:

Oregon North Zone, NAD 83/91, U.S. Survey Foot:

N = 680534.24

E = 8725956.45

RECEIVED BY .

Umatilla County Surveyor

Date 2-95

Rec'd by KK

No. 95-16-C

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/96

RECEIVED BY

Umatilla County Surveyor

Date R-95

Rec'd By KK

No. 95-16-C