

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**History of original corner establishment:**

None.

**Description of corner evidence found:**


None.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

At a computed position, I set a 3-1/4" aluminum cap marked per the diagram on a 2-1/2" x 30" aluminum pipe monument from which:

- 31" Douglas Fir bears N.33°E., 15.0 feet, scribed "NE1/16S6BT".
- 28" Douglas Fir bears S.57°E., 9.8 feet, scribed "XBT".

All new bearing trees are single blazed and scribed with brass washer "PLS2535" attached to the BT portion. Appropriate signs have been attached to all bearing trees as required by this US Forest Service contract. 20° declination was used. Fieldwork was performed in July and August 2002.



REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Michael P. LeJeune*

OREGON 11/06/02  
JAN. 21, 1992  
MICHAEL P. LE JEUNE  
2535

*EXPIRES 12/31/02*

Prepared by: White Shield, Inc.  
2515 W. Falls Ave.  
Kennewick, WA 99336

Michael P. LeJeune,  
Oregon PLS. 2535

Office of ....County Surveyor....., County of ....Umatilla....., State of Oregon, I hereby certify that the within

instrument was filed in this office for record on the .....day of .....

*David H. L.*  
.....  
(County Official)

..... by .....  
(Deputy)

RECEIVED BY  
Umatilla County Surveyor  
Date 11-02  
Rec'd By KL  
No. 02-273-B