

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner established in 1882 by Herman D. Gradon, US Deputy Surveyor, under Contract Number 452. The Surveyor General's records state:

Set a basalt stone 16x16x8 ins 11 ins in the ground for 1/4 sec cor marked 1/4 on N-face from which:
A fir 28 ins diam. bears S.50°W. 135 lks dist. marked 1/4 S.B.T.
No other tree within limits and raised a mound of stone alongside.

The 1/4 section was monumented in 1982, A. Joseph Garrison, Cadastral Surveyor under Bureau of Land Management Group No. 1000. The field notes state:
The corner determined at record bearing and distance from the original bearing tree:
A fir, 32 ins. diam., bears S.50°W., 135 lks. dist., with scribe mark 1 visible on partially opened blaze.

At the corner point, set aluminum post, 28 ins. long, 2-1/2 ins. diam., 14 ins. in the ground, to solid rock, in a mound of stone, 3 1/2 ft. base, to top, with aluminum cap, from which a new bearing tree
An alder, 11 ins. diam., bears N.12°E., 58 lks. dist., mkd. 1/4 S4 BT.



Description of corner evidence found:

Found 3-1/4" BLM aluminum cap marked per the diagram on 2-1/2" pipe, 12 inches above ground in a large pile of stones.

18" Cottonwood bears N. 11° E., 38.3 feet with healed face. (BLM bearing tree).
42" Fir bears S.50°W., 89.1 feet with a healed face. (1882 bearing tree).

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 5/8" x 24" rebar with 1-1/2" aluminum cap, bears N.85°E., 21.7 feet, stamped WSI/RM 21.7, 2535.
Set 5/8" x 24" rebar with 1-1/2" aluminum cap, bears S.80°W., 19.9 feet, stamped WSI/RM 19.9, 2535.

Reference monuments have an arrow pointing towards the corner. Appropriate signs have been attached to all bearing trees as required by this US Forest Service contract. 20° declination was used. Fieldwork was performed in May 2002.

REGISTERED PROFESSIONAL LAND SURVEYOR
Michael P. LeJeune
OREGON 11/06/02
JAN. 21. 1992
MICHAEL P. LE JEUNE
2535
Expires 12/31/02

Prepared by: White Shield, Inc. Michael P. LeJeune,
2515 W. Falls Ave. Oregon PLS. 2535
Kennewick, WA 99336

Office ofCounty Surveyor....., County ofUmatilla.....,State of Oregon, I hereby certify that the within

instrument was filed in this office for record on theday of
David Allen
....., by
(County Official) (Deputy)

RECEIVED BY
Umatilla County Surveyor
Date 11-02
Rec'd By KK
No. 02-273-B