


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Not applicable

Description of corner evidence found:

None



Description of monument and accessories I established to perpetuate the original location of this corner:

At a computed position, set a 3-1/4" aluminum cap marked per the diagram on 2-1/2" x 30" aluminum pipe, 6 inches above the ground. From which:

- 16" Douglas Fir bears N.29°W., 38.0 feet, scribed "NW 1/16 S9 BT".
- 28" Ponderosa Pine bears S.62°E., 53.6 feet, scribed "NW 1/16 S9 BT".

All new bearing trees are single blazed and scribed with brass washer "PLS2535" attached to the BT portion. Appropriate signs have been attached to all bearing trees as required by this US Forest Service contract. 20° declination was used. Fieldwork was performed in May 2002.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Michael P. LeJeune

OREGON 11/06/02
JAN. 21, 1992
MICHAEL P. LE JEUNE
2535

EXPIRES 12/31/02

Prepared by: White Shield, Inc.
2515 W. Falls Ave.
Kennewick, WA 99336

Michael P. LeJeune,
Oregon PLS. 2535

Office ofCounty Surveyor....., County ofUmatilla.....,State of Oregon, I hereby certify that the within

instrument was filed in this office for record on theday of
David H. Allen (County Official), by (Deputy)

RECEIVED BY
Umatilla County Surveyor
Date 11-02
Rec'd By BK
No. 02-273-B