

# CERTIFIED RECORD OF LAND CORNER MONUMENTATION

### History of original corner establishment:

Corner established in 1882 by Herman D. Gradon, US Deputy Surveyor, under Contract Number 452. The Surveyor General's records state:

Set a basalt stone 20x9x5 ins 15 ins in the ground for the 1/4 sec cor, marked 1/4 on the W, from which:

A fir 6 ins diam bears S.20°E., 94 lks dist, marked 1/4SBT

A pine 30 ins diam bears N.50°W., 142 lks dist, marked 1/4SBT

1998, by Kaiser/Griffin/ Seibold, Cadastral Surveyors under Bureau of Land Management Group No. The BLM records state:


Point for the 1/4 sec. cor. of sec. 8 and 9, at a proportionate distance; there is no remaining evidence of the original corner.

Set a stainless steel post, 28 ins. long, 2-1/2 ins. diam., 22 ins. in the ground, in a mound of stone, 3 ft. base, to top, with brass cap, from which:

The marks BXO on top and 1 ft. from the W. edge of a boulder, 5-1/2 ft. x 4 ft. x 2 ft., bears N.77°E., 4 lks. dist.

A grand fir, 30 ins. diam., bears N.85°W., 27 lks. dist., mkd. 1/4 S8 BT.

Deposited a magnet in a white plastic case at the base of the stainless steel post.



### Description of corner evidence found:

Found 3-1/4" BLM brass cap marked per the diagram at base of rock talus slope, buried, from which; 30" Fir bears N.85°W., 17.8 feet, with visible scribing.

A 5.5' x 4' x 2' boulder bears N.77°E., 2.6 feet. "XBO" chiseled on boulder.

### Description of monument and accessories I established to perpetuate the original location of this corner:

Set chisel "X" on top of a 3' x 2' x 5' rock bears N.50°W., 8.0 feet.

Set chisel "X" on West face on a large outcrop of rock bears S.50°E. 12.9 feet.

Reference monuments have an arrow pointing towards the corner. Appropriate signs have been attached to all bearing trees as required by this US Forest Service contract. 20° declination was used. Fieldwork was performed in May 2002.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Michael P. LeJeune*

OREGON  
JAN. 21, 1892  
MICHAEL P. LE JEUNE  
2535

11/06/02  
*EXPIRES 12/31/02*

Prepared by: White Shield, Inc.  
2515 W. Falls Ave.  
Kennewick, WA 99336

Michael P. LeJeune,  
Oregon PLS. 2535

Office of ....County Surveyor....., County of ....Umatilla.....,State of Oregon, I hereby certify that the within

instrument was filed in this office for record on the .....day of .....<sup>20</sup>.....

*David H. Kline*  
(County Official)

RECEIVED BY

Umatilla County Surveyor

(Deputy)

Date 11-02

Rec'd By KK

No. 12-273-B